# This Page Is Inserted by IFW Operations and is not a part of the Official Record

## **BEST AVAILABLE IMAGES**

Defective images within this document are accurate representations of the original documents submitted by the applicant.

Defects in the images may include (but are not limited to):

- BLACK BORDERS
- TEXT CUT OFF AT TOP, BOTTOM OR SIDES
- FADED TEXT
- ILLEGIBLE TEXT
- SKEWED/SLANTED IMAGES
- COLORED PHOTOS
- BLACK OR VERY BLACK AND WHITE DARK PHOTOS
- GRAY SCALE DOCUMENTS

## IMAGES ARE BEST AVAILABLE COPY.

As rescanning documents will not correct images, please do not report the images to the Image Problem Mailbox.

#### PCT

## WORLD INTELLECTUAL PROPERTY ORGANIZATION International Bureau



#### INTERNATIONAL APPLICATION PUBLISHED UNDER THE PATENT COOPERATION TREATY (PCT)

(51) International Patent Classification 6:
C12Q 1/68

A1 (43) International Publication Number: WO 99/31278
(43) International Publication Date: 24.func 1999 (24/6.99)

(23) International Application Number: PCTF/US98/26718
(22) International Filing Date: 15 December 1998 (15.12.98)

(63) Related by Continuation (CON) or Confinuation-in-Part

(CJP) to Kartier Application
US

08/990,851 (CIP) 15 December 1997 (15.12.97)

15 December 1997 (15.12.97)

(71) Applicants (for all designated States except US): SEQUENOM, INC. [US/US]: 11555 Sorrento Valley Road, San Diego, CA 92121 (US). KOREA ADVANCED INSTITUTE OF SCIENCE AND TECHNOLOGY [KR/KR]: 373-1, Kusang dang, Yusang-gu, Taejon 305-701 (KR).

(71)(72) Applicant and Inventor: O'DONNELL, Maryanne, J. [US/US]; Aparlment 38F, 65 India Row. Buston. MA 02110 (US).

(72) Inventors; and

(30) Priority Data:

08,990,851

Filed on

(75) Inventors/Applicants (fix US only): KANG, Changwan [KR/KR]; Pxpo Apartment 505 401, 464-1, Jeonmin-dong, Yusong-gu, Turjon 305-290 (KR), KWON, Young Suo [KR/KR]; 25-2, Mangwol-dong, Puk-gu, Kwangju 500-500 (KR), KIM, Young, Tur [KR/KR]; Sungwon Apartment 2-204, 162, Songpa 2 dong, Songpa gu, Seoul 138-172 (KR), KÖSTER, Hichen [DE/US]; 8636-C Via Mallorta Drive, La Joha, CA 92037 (US), LITTLE, Darrel, P. [US/US]; 393 Glendale Lake Road, Patton, PA 18508 (US), XJANG, Guobing [CN/US]; 8655 Anthroneda Road, San Diego, CA 92121 (US), LOUGH, David, M. [GR/GB]; 32 Deanhead Road, Eyenronti, Berwickship: TD14 55A (GB), CANTOR, Charles (US/US); H. Bay State Road #5, Boston, MA 02215 (US).

(74) Agent: SEIDMAN, Stephanie, L.; Heller Ehrman White & McAuliffe, Suim 700, 4250 Executive Squere, La Jolla, CA 92037 (US).


(81) Designated States: AL. AM, AT, AU, AZ, BA, BB, BG, BR, BY, CA, CH, CN, CU, CZ, DE, DK, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, ICR, KZ, LC, EK, LR, LS, LT, LH, LV, MD, MG, MK, MN, MW, MX, NO, NZ, PL, PT, RO, RU, SD, SB, SG, SI, SK, SL, TI, FM, TR, TT, CA, UG, US, UZ, VN, YU, ZW, ARIPO patent (GH, GM, KB, LS, MW, SD, SZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), Hindocan patent (AT, BL, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LC, MC, NL, PT, SE), OAPJ patent (BT, BI, CF, CG, CI, CM, GA, GN, GW, ML, MK, NE, SN, TD, TG).

#### Published

With international search report.

Before the expiration of the time limit for unrealing the clams and to be republished in the event of the receipt of aniendments.

(54) Title: MASS SPECTROMETRIC METHODS FOR SEQUENCING NUCLEIC ACIDS



(57) Abstract

A mass spectrumetric method for sequencing nucleic soids using RNA polymerases, including DNA-dependent and RNA-dependent RNA polymerases, is provided. The methods include use the RNA polymerase is to generate a set of nested RNA transcripts, which are analyzed mass spectrometry. A method of identifying transcriptional terminator sequences or attenuator sequences is also provided,

### FOR THE PURPOSES OF INFORMATION ONLY

Codes used to identify States party to the PCT on the front pages of pamphlets publishing international applications under the PCT.

AL	Alberrin	K\$	Spain	6.3	Linestini	ន	Slovenia
ADR	Annous Annous	1/1	-in1mal	6.00	1.irักเลกรัจ	ъĸ	8'oyakia
AT	Austria	ľk	Firmo <del>r</del>	1.0	Luxerabourg	60	senegal
VI.	Australia	GA	CK 2011	LV	Lavia	<b>SZ</b>	5 w av. land
AZ	Azertaijan	GB	United Kingdom	MC	r-tonnes-1	Tυ	Cond
BA	Bosnia and Herzegovina	GI	Saugia	MD	Republic of Violdani	TG	T(4)
TDTD	Darhados	CH	Clima	MG	Mexhagoscar	ТJ	Tapk:s.an
ne.	Delgium	GN	Cuinos.	MK	Tai: (urmer Yugoslav	T'M	1, 13 mornta
DF.	Bukina Fato	GR	Giraco		Reguld c of Matedonia	TR	Тако
n.C	Balgaria	ΠO	) lungary	VΠ.	Mati	TT	Trinidal and Tobago
BI	Deniu:	TE.	heland	ษณ	Murgotia.	UA	(Persine
BR	Drugil	TI,	lyzaci	MR	Mauratanae	DC.	Ligimila
HY	nelaris	15	Teelingi	му	Maissi	US	Laired States of Americ
CA	Canada	LT	Tri.ly	MX	Mexico	[17.	Lizhekistan
CF	Central Athican Republic	))·	ווניוןה.	NR	Ni acc	VK	Vier Yara
ĊĠ	Congr	M.F.	Kenya	NL.	Netherlands	YL	Yugos:xvla
CH	Serizerland	N'C	Kyrgyaxtan	ND	AULE: SV.	210	Zimbeawo
CI	Cate d'Espire	KP	Ogmostania Feogle's	N6	Yes: Zealand		
CM	Cameroon.		Republic of Korea	PI.	cafo <sup>c</sup>		
CV.	Chira	КМ	Republic of Kores	<b>71</b> .	?отнуы <sup>*</sup>		
CL	Cuta	KZ	Kazoksram	RO	Remaria		
CZ	Czech Republic	LC	Soiry Tarcia	RU	Rossan Federation		
DE	Gein's vy	ū	Liebtensein	SD	5 molen		
DK	Dynamic	EIG	Sr Lark:	3F	Sweden		
EE	Estu-ra	นเ	Libera	зG	Singapere		

## MASS SPECTROMETRIC METHODS FOR SEQUENCING NUCLEIC ACIDS RELATED APPLICATIONS

Benefit of priority is claimed to U.S. application Serial No.08/990,851, filed December 15, 1997, to Changwon Kang, Young-5 Soo Kwon, Young Tae Kim, Hubert Köster, Daniel Little, Maryanne O'Donnell, Guobing Xiang, Charles Cantor and David Lough, entitled "MASS SPECTROMETRIC METHODS FOR SEQUENCING NUCLEIC ACIDS". Where permitted, the subject matter of this application is incorporated herein by reference in its entirety.

The subject matter of this application is related to the following copending applications, international applications and patents: U.S. Patent Nos. 5,605,798, 5,622,824 and 5,547,835, 5,691,141, International PCT application No. WO 98/20019, WO 98/20166 and WO 97/42348. Where permitted, the subject matter of each of these applications and patents is incorporated herein in its entirety. 15

#### BACKGROUND OF THE INVENTION

Nucleic acid sequencing methods are important and powerful tools in the molecular biologist's repository of techniques for assessing and understanding gene expression and regulation. Methods for sequencing 20 DNA molecules include chemical degradation sequencing (Maxam et al. (1977) Proc. Natl. Acad. Sci. USA 74: 560, see, also, Ambrose et al. (1987) Methods Enz. 152: 522) and chain termination sequencing (Sanger et al. (1977) Proc. Natl. Acad. Sci. USA 74: 5463). The Maxam-Gilbert sequencing method is a degradative method that relies on 25 specific cleavage of DNA fragments. A fragment of DNA, which is radiolabeled at one end, is partially cleaved in five separate chemical reactions. Each reaction is specific for a type of base or a base so that fiv populations of labeled fragments of differing lengths are generated.

The populations of fragments are resolved by polyacrylamide gel electrophoresis (PAGE).

The chain termination or Sanger method relies on a DNA synthesis. Single-stranded DNA is used as a template and labeled primers are used 5 to initiate formation of complementary strands. The synthesis reaction is run in the presence of the four deoxynucleotides (dNTPs), dATP, dTTP. dCTP and dGTP and one of the four dideoxynucleotides (ddNTPs), ddATP, ddTTP, ddCTP, and ddGTP. The complementary strands are prematurely terminated along the chain by addition of dideoxynucleotides 10 to the growing chains. By starting with four reaction mixtures, which each contain one of the four ddNTPs, sets of strands terminating in A, C, G and T are generated. Each reaction mixture is electrophoresed in one lane of a polyacrylamide gel that resolves fragments that differ by a single base in length.

These methods are primarily designed for sequencing singlestranded DNA, which is produced by denaturing the DNA and separating the single strands, or by other methods, such as cloning into singlestranded phage vectors. These sequencing methods rely on reactions that produce an array of fragments that differ in length by a single base 20 and terminate in an identifiable base. The fragments are resolved by size using PAGE and are detected using a label, such as a radioisotope. Because the resolution of bands on an electrophoretic gel decreases exponentially as the length of the DNA fragments increase, these methods only permit DNA fragments of up to about 300 to 400 25 nucleotides to be sequenced.

The target DNA can also be amplified using the polymerase chain reaction (PCR) (see, e.g., Mullis et al. (1986) Cold Spring Harbor Symp. Quant. Biol. 51: 263; U.S. Patent No. 4,683,202 to Mullis et al.), which results in an amplified concentration of the duplex target DNA. A

number of methods have been used to generate single-stranded templates directly from PCR for subsequent sequencing. For example, radio-labeled primer that is specific for only one strand may be used. Alternatively, PCR may be run under conditions such that one primer is at limited concentration. Once the primer that is at the limited concentration is exhausted, the second strand is amplified at a linear rate through succeeding cycles (Gyllenstein et al. (1988) Proc. Natl. Acad. Sci. 85: 7652; Mihilovic et al. (1989) BioTechniques 7:14).

There are numerous sequencing strategies in use. The selected 10 strategy depends upon the purpose for which the DNA is sequenced and the amount of information available about the DNA prior to sequencing. For example, if the target DNA is sequenced in order to confirm that a particular mutation has been introduced into the DNA, it may only be nacessary to sequence a small region of DNA. If the DNA fragment is an 15 unknown gene or portion of a gene for which a sequence must be accurately determined, then it may be necessary to sequence the entire fragment. Because the sizes of fragments that can be sequenced are limited to about 400 bases, DNA fragments longer than this size must be cleaved. Cleavage may be random, by subcloning segments of the target 20 DNA. The subcloned fragments, which include overlapping fragments, are then sequenced, and ordered using a computer program (see, e.g., Staden (1986) Nucl. Acids Res. 14:217). Alternatively, the DNA may be systematically subcloned by generating and sequencing overlapping or nested mutants or by other ordered approaches.

The Sanger chain termination method and other sequencing methods rely on the use of single-stranded template by cloning the target DNA into single-stranded phage vectors. The use of plasmids as vectors for the target DNA, however, is preferred over the use of phage DNA for reasons, which include the variety of available plasmids, the ase with

which plasmids are manipulated, and the greater stability of inserted DNA in plasmids compared to phage vectors. Consequently, methods for sequencing in which the target DNA is cloned into plasmid DNA, rather than into a single-stranded phage DNA (see, e.g., Wallance et al. (1981)

5 Gene 16: 21-26; Guo et al. (1982) Nucl. Acids Res. 10: 2065-2084; Vieira et al. (1982) Gene 19: 259-268) have been developed.

These methods are designed to only sequence one strand of the target DNA at a time (see, e.g., Chen et al. (1985) DNA 4: 165-170; Hattori et al. (1986) Anal. Biochem. 152: 232-238; Mierendorf et al. (1987) Methods Enzymol. 152: 556; Mehra et al. (1986) Proc. Natl. Acad. Sci. USA 83: 7013-7017). Use of double-stranded DNA, however, avoids the subcloning or isolation of single-stranded DNA fragments, which are used for the dideoxy chain terminator sequencing reactions. The use of double-stranded DNA, however, had been limited because of the poor template quality of denatured duplex DNA. As a result, these methods had not provided as accurate sequence data as provided by methods in which the DNA is cloned into a single-stranded vector.

Recently, the problems associated with template quality have been solved by the development of methods that use plasmids that include sites, adjacent to the complementary strands of the inserted DNA, to which strand-specific primers may be efficiently hybridized. By virtue of these methods each of the single strands of double-stranded DNA can be sequenced directly from plasmid DNA without prior subcloning into phage vectors (see, a.g., Chen et al. ((1985) DNA 4: 165-170 and Chi et al. (1988) Nucl. Acids Res. 16: 10382). A strand specific synthetic primer is annealed to covalently closed circular DNA, which has been denatured by heat or alkali, before proceeding with dideoxy sequencing reactions. Alternatively, the primer can be annealed to open circle

25

double-stranded plasmid DNA, which has been denatured by alkali, as a template (see, Hattori et al. ((1986) Anal. Biochem. 152: 232-238). The double-stranded DNA is denatured with alkali or heat prior to sequencing using the Sanger method, which is performed at 37° C or higher. The use of different "forward" and "reverse" primers, which are each complementary to the lac Z sequences adjacent to the EcoRI site in Agt11, for separately sequencing each strand of DNA that has been cloned into Agt11 has also been described (see, Mehra et al. (1986) Proc. Natl. Acad. Sci. USA 83: 7013-7017).

Plasmids with oppositely oriented promoter regions, which are used in methods which involve transcription, are also used as vehicles for target DNA which is to be sequenced. Each promoter region serves as a distinct specific priming site for sequencing the inserted DNA. Such plasmids are commercially available. For example, the twin promoter plasmid pGEM<sup>TM</sup> contains the bacteriophage SP6 and T7 RNA polymerase promoters in opposite orientations (Mierendorf et al. (1987) Meth. Enzymol. 152: 556-562) which can generate transcripts for sequencing.

Most methods for sequencing nucleic acids require the use of polyacrylamide get electrophoresis (i.e., PAGE) that can result in sequencing artifacts or require detectable labels, such as radioisotopes, enzymes, or fluorescent or chemiluminescent moieties. Methods for sequencing of DNA using mass spectromeric detection are also in use (see, U.S. Patent No. 5,547,835). These methods primarily rely on sequencing of DNA.

Using DNA sequencing methodologies, the entire sequence of the human genome ultimately will be determined. The knowledge of the complete sequence of the human genome DNA will help to understand, to diagnose, to prevent and to treat human diseases. To be able to tackle successfully the determination of the approximately 3 billion base

pairs of the human genome in a reasonable time frame and in an economical way, rapid, reliable, sensitive and inexpensive methods are required.

Therefore it is an object herein to provide additional methods for sequencing. In particular, it is an object herein to provide mass spectrometric methods of sequencing nucleic acids using RNA polymerase. It is a further object herein to provide methods of sequencing nucleic acids in an array format using RNA polymerase in which nucleic acid probes are immobilized to supports at high densities to facilitate mass spectrometric detection. It is also an object herein to provide methods for identifying transcriptional terminator sequences using mass spectrometric methods.

#### SUMMARY OF THE INVENTION

Methods for sequencing nucleic acids, particuarly DNA, using RNA transcripts are provided. In particular, methods for sequencing nucleic acids using RNA polymerases, including DNA-dependent and RNA-dependent RNA polymerases, are provided. RNA transcripts are analyzed by mass spectrometry.

In practicing the methods, a DNA molecule comprising a promoter and target nucleic acid sequence operatively linked to the promoter is transcribed with an RNA polymerase that recognizes the promoter under conditions that generate a nested set of RNA transcripts that include the target is produced. The molecular weight of the transcripts are determined by mass spectrometry to thereby determine the nucleic acid sequence of the target sequence. The DNA molecule that contains the nucleic acid and target is preferably immobilized.

In certain embodiments, the methods use a double-stranded promoter-containing fragment with a single-stranded region at one end,

20

which captures a molecule that contains the target DNA. In these embodiments, the target DNA is preferably single-stranded.

In preferred embadiments, the promoter-containing nucleic acid is covalently coupled via the 3'-end of the noncoding (antisense) strand or 5 5'-end of the coding strand to a solid support. Coupling can be by any method known to those of skill in the art, such as via a thiol linkage. For example, 5'- or 3'-thiolated DNA is prepared and linked at to a aminosilane-treated solid support. The linkage may be direct or via a linker group. The resulting immobilized molecules are preferably arranged in an array format,

A double-stranded nucleic acid molecule encoding a promoter sequence can obtained from any source, such as bacteria, viruses, bacteriophages, plants and eukaryotic organisms, or assembled by synthetic protocols. It is engineered using so that the resulting fragment 15 contains a single-stranded region of at least a 5 nucleotides at the 3'-end of the coding (sense) strand. This single-stranded region is designed such that it is complementary to a region of the nucleic acid to be sequenced or to a common overlapping sequence, such as a restriction endonuclease site.

The target nucleic acid, which inloudes the region of nucleic acid to be sequenced is single-stranded or double-stranded but includes a single-stranded 3'-end, is hybridized to the complementary sequences of the promoter-containing DNA. Hybridization is performed either before or after immobilization. The hybridization of the two nucleic acid 25 molecules introduces one or more "nicks" in the hybrid at the junction(s) of the adjacent nucleic acid molecules. In certain embodiments, nicks in the coding or non-coding strand, preferably the coding strand, are ligated by the addition of an appropriate nucleic acid ligase prior to initiating transcription.

25

The methods preferably employ any suitable strategy for generating nested RNA transcripts. The preferred methods rely on a modified Sanger sequencing strategy in which RNA polymerase is used to generate a set of nested RNA transcripts obtained by base-specific 5 chain termination. These are analyzed by mass spectrometry. A modified Gilbert-Maxam strategy is also contemplated. In this method, the transcripts are cleaved with base-specific RNases to produce basespecifically terminated fragments and the molecular weights are then assess by mass spectrometry.

Transcription is initiated from the promoter by the addition of the appropriate RNA polymerase in the presence of ribonucleoside triphosphates and a selected base-specific chain terminating 3'deoxyribonucleoside triphosphate. In preferred embodiments, the transcription mixture also contains modified ribonucleoside triphosphates 15 and ribonucleotide analogs ribonucleotide triphosphate analogs that reduce secondary structure of the resulting RNA transcripts and/or increase the fidelity of termination and turnover of the RNA polymerase enzyme thereby increasing the amount of RNA transcript available for analysis.. These analogs include, but are not limited to: inosine 5'-20 triphosphate (FTP), which reduces secondary structure, 4-thio uridine 5'triphosphate (UTP) and 5-bromo UTP or 5'-iodo CTP, which increase the fidelity of termination and turnover of the RNA polymerase enzyme thereby increasing the amount of RNA transcript available for analysis. The resulting RNA transcripts are analyzed by mass spectrometry.

in other embodiments, the sample further contains a matrix material for mass spectrometry for analysis by matrix-assisted laser desorption/ionization mass spectrometry (MALDI) and preferably further uses time-of-flight (TOF) analysis. The sequence of the nucleic acid is obtained by aligning the observed mass of the chain-terminated RNA

transcripts obtained from sequencing reactions containing each of the four chain-terminating bases.

The methods of sequencing provided herein may be used for diagnostic applications. Diagnostic applications, include methods for 5 determination of the presence of genetic alterations in a known target nucleic acid. For example, a region of the target nucleic acid is amplified and the nucleic acid strand corresponding to the noncoding strand is isolated. The nucleic acid probe containing the promoter may be isolated from a natural source or assembled synthetically by hybridizing two 10 complementary oligonucleotides to form a promoter sequence. A single-stranded region of at least 5 nucleotides that is complementary to a region of the nucleic acid to be sequenced or to a common sequence is introduced by recombinant means at the 3'-end of the coding strand. In preferred embodiments, the promoter-containing nucleic acid is 15 covalently coupled via the 3'-end of the noncoding strand or 5'-end of the coding strand to a solid support and, more preferably, is a 5'- or 3'thiolated DNA linked at high densities to a aminosilane-treated solid support. The linkage may be in the absence or presence of a linker group and is preferably arranged in an array format.

A single-stranded 3' overhang of the nucleic acid to be sequenced, in single-stranded or double-stranded form, is hybridized to the complementary sequences of the noncoding strand and, in some embodiments, the nick(s) between one or more nucleic acid strands is/are ligated prior to transcription. Transcription is initiated using the 25 appropriate RNA polymerase in the presence of ribonucleoside triphosphates and a selected base-specific chain terminating 3'deoxyribonucleoside triphosphate. In preferred embodiments, the transcription mixture may also contain inosine 5'-triphosphate and/or one or more modified ribonucleoside triphosphates to facilitate analysis of the

RNA transcripts. The RNA transcripts are analyzed by mass spectrometry, preferably using MALDI-TOF.

When used in array formats, a panel of promoter-containing nucleic acid probes can be constructed and linked in an array such that the target nucleic acid is permuted along the entire sequence, e.g., the coding sequence of a gene, allowing for the determination of the nucleic acid sequence of the entire gene during a single reaction sequence.

Methods of identifying transcriptional terminator and attenuator sequences are also provided. By modifying transcription conditions to produce full-length transcripts, transcriptional terminator sequences, such as rho-dependent and rho-independent terminators, may be identified using mass spectrometric methods. In practicing the methods, a single-stranded region of the 3'-end of the target nucleic acid to be sequenced is hybridized to a complementary sequence at the 3'-end of the coding strand a promoter-containing nucleic acid probe. In preferred embodiments, the promoter-containing nucleic acid is covalently coupled via the 5'-end of the noncoding strand or 3'-end of the coding strand to a solid support and, more preferably, is a 5'- or 3'-thiolated DNA linked at high densities to a aminosilane-treated solid support. The linkage may be in the absence or presence of a linker group and is preferably arranged in an array format.

Transcription is initiated in the absence or presence of modified RNA triphosphate analogs that increase the efficiency of RNA polymerase termination at such terminator sequences, such as 4-thio UTP, 5-bromo UTP or 5'-iodo CTP. In certain embodiments, nicks in one or more strand may be ligated by the addition of an appropriate nucleic acid ligase prior to initiating transcription (i.e., adding a DNA or RNA ligase). The mass of the terminated RNA transcripts is determined by mass spectrometry. The observed mass is indicative of the location of the terminator-dependent

arrest of transcription and by comparing the alignment of the sequence immediately preceding the site of transcriptional termination from distinct genomic locations, terminator and attenuator sequences may be identified for different RNA polymerases.

#### 5 DESCRIPTION OF THE DRAWINGS

Figure 1 illustrates a system for preparing arrays of a sample material for analysis.

Figure 2 illustrates a pin assembly suitable for use with the system depicted in Fig. 1 for implementing a parallel process of dispensing material to a surface of a substrate.

Figure 3 depicts a bottom portion of the assembly shown in Fig. 2.

Figure 4 depicts an alternative view of the bottom portion of the pin assembly depicted in Fig. 2.

Figures 5A-5D depict a method for preparing an array of sample 15 material.

Figures 6A-6B depict an alternative assembly for dispensing material to the surface of a substrate.

Figure 7 is a schematic showing covalent attachment of oligodeoxynucleotides to a silicon dioxide surface as described herein. In particular, silicon dioxide was reacted with 3-aminopropyltriethoxysilane to produce a uniform layer of primary amino groups on the surface. A heterobifunctional crosslinking agent was then reacted with the primary amine to incorporate an iodoacetamide-group. An oligodeoxynucleotide containing a 3'- or 5'-disulfide (shown as the 5') was treated with tris-(2-carboxyethyl) phosphine (TCEP) to reduce the disulfide to a free thiol, which was then coupled to the iodoacetamido-surface.

Figure 8 is a graph which plots conjugation of oligodeoxynucleotide probes to a silicon surface as a function of TCEP concentration used in the disulfide reduction.

Figure 9 is a matrix assisted laser desorbtion/ionization-time-of-flight (MALDI-TOF) mass spectrum of a silicon wafer with the oligodeoxynucleotide sequence denoted "TCUC" (5'-GAATTCGAGCTCG GTACCCGG-3'; SEQ ID NO; 1) covalently bound essentially as described in Figure 7 and the oligodeoxynucleotide sequence denoted "MJM6" (5'-CCGGGTACCGAGCTCGAATTC-3'; SEQ ID NO; 2) hybridized thereto.

Figure 10 depicts one embodiment of a substrate having wells etched therein that are suitable for receiving material for analysis.

Figure 11 depicts one example of spectra obtained from a linear time of flight mass spectrometer instrument and representative of the material composition of the sample material on the surface of the substrate depicted in Fig. 10.

Figure 12 depicts molecular weights determined for the sample material having spectra identified in Fig. 11.

Figure 13 is a schematic of a 4 x 4 (16-location) DNA array on the surface of a silicon wafer with the thiol-containing oligonucleotide

20 molecules denoted "Oligomer 1", (5'-CTGGATGCGTCGGATCATCTTTTTT-(S)-3'; SEQ ID NO; 5), Oligomer 2 (5'-(S)-CCTCTTGGGAACTGTGTAGTATT-3'; SEQ ID NO; 6) and "Oligomer 3" (SEQ ID NO; 1; a free thiol derivative "TCUC" oligonucleotide of EXAMPLE 1) covalently bound to 16 locations on the surface of the silicon wafer essentially as described in EXAMPLE 2.

Figure 14 is a schematic of the hybridization of specific oligonucleotides to each of the 16 locations of the DNA hybridization array of Figure 13 with the Oligomer 1 complementary oligonucleotide (5'-GATGATCCGACGCATCAGAATGT-3'; SEQ ID NO: 7) b und to

15

Oligomer 1, the Oligomer 2 complementary oligonucleatide (5'-AATACTACACAG-3'; SEQ ID NO: 8) bound to Oligomer 2 and the Oligomer 3 complementary oligonucleotide (5'-CCGGGTACCGAGCTCGAATTC-3'; SEQ ID NO: 2) bound to Oligomer 3.

Figure 15 is a representative MALDI-TOF mass spectrum of a 4 x 4 (16-location) DNA array on a silicon wafer shown schematically in Figure 15. The spectrum reveals a single, predominant signal of an experimental mass-to-charge ratio in each location corresponding to the specific hybridized oligonucleotides. The 2+ indicates the position of a 10 doubly charged molecule used as a reference standard during MALDI-TOF MS analysis. The \* denotes residual amounts of contaminating oligonucleotide that remain on the surface of the chip following washing procedures. The relative position of the \* signal reveals the approximate size of the contaminating oligonucleotide.

Figure 16 is a representative MALDI-TOF mass spectrum of an 8 x 8 (64-location) DNA array. The spectrum reveals a single, predominant signal of an experimental mass-to-charge ratio corresponding to the predicted specific hybridized oligonucleotides. The \* denotes residual amounts of contaminating oligonucleotide that remain on the surface of 20 the wafer following washing procedures. The relative position of the \* signal reveals the approximate size of the contaminating oligonucleotide.

Figure 17 shows the nucleotide sequence of a DNA molecule (SEQ ID No: 10) assembled by hybridizing a 55-mer oligonucleotide to a complementary 25-mer oligonucleotide (SEQ ID No: 11) and a 25 complementary 30-mer oligonucleotide (SEQ ID No: 12). The resulting double-stranded DNA encodes a SP6 promoter (nt 1-18 of SEQ ID No: 10) and has a single nick in the coding strand of the molecule at nt + 7relative to the start of transcription from the SP6 promoter. The position

of the nick and the start of transcription initiation from the SP6 promoter are indicated.

## DETAILED DESCRIPTION AND PREFERRED EMBODIMENTS Definitions

Unless defined otherwise, all technical and scientific terms used herein have the same meaning as is commonly understood by one of skill in the art to which this invention belongs. All patents and publications referred to herein are incorporated by reference herein.

As used herein, the term "nucleic acid" refers to oligonucleotides or polynucleotides such as deoxyribonucleic acid (DNA) and ribonucleic acid (RNA) as well as analogs of either RNA or DNA, for example, made from nucleotide analogs, any of which are in single or double-stranded form and also PNA. Nucleic acid molecules can be synthetic or can be isolated from a particular biological sample using any number of procedures which are well-known in the art, the particular procedure chosen being appropriate for the particular biological sample.

As used herein, nucleotides include nucleoside mono-, di-, and triphosphates. Nucleotides also include modified nucleotides such as phosphorothioate nucleotides and deazapurine nucleotides. A complete set of chain-elongating nucleotides refers to four different nucleotides that can hybridize to each of the four different bases comprising the DNA template.

As used herein, a nucleic acid promoter-containing probe refers to a nucleic acid fragment that includes a double-stranded region encoding a promoter and a single-stranded region that contains at least 5 nucleotides at the 3'-end of the coding (sense) strand relative to the promoter. The at least 5 nucleotides are selected to be complementary to a single-stranded region at the 3'-end of a nucleic acid containing the target nucleic acid of interest. Reference to the 3'-end refers to the antisense

strand if the target is contained in a double-stranded molecule. When the target is double-stranded the resulting molecule has nicks in the coding and non-coding strands.

Alternatively, the single-stranded region of the nucleic acid

promoter-containing probe includes at least about 5 nucleotides at the 5'end of the noncoding (antisense) strand (relative to the promoter) that
are complementary to at least about five nucleotides at the 5'-end of the
coding strand of a target nucleic acid. In this embodiment, the target
must be double-stranded. Following hybridization, the resulting
molecule has nicks in the coding and non-coding strands.

In all embodiments, nicks can be ligated prior to transcription. As shown herein, however, if the nicks are at a sufficient distance, preferably at least about +7 nucleotides, it is not necessary to ligate.

As used here in, the target nucleic acid is the nucleic acid

molecule to be sequenced. It can be part of a larger molecule. The
molecule that contains the target nucleic acid can contain or can be
modified to contain at least about 5 nucleotides whose sequence is
designed to be fully complementary to at least 5 contiguous nucleotides
at the 3' end of the over hang on the promoter-containing capture probe

(or 5' end depending upon the configuration selected). The target
nucleic acid can be double-stranded, with a 3' or 5' single-stranded
overhang, or single-stranded. RNA polymerases can and do transcribe
single-stranded molecules, particularly, once the ternary complex is
formed. The target may also be RNA or PNA (protein nucleic acid formed
by conjugating bases to an amino acid backbone; see, e.g., Nielsen et
al. (1991) Science 254:1497).

As used herein, nucleic acid synthesis refers to any process by which oligonucleotides or polynucleotides are generated, including, but not limited to processes involving chimical or enzymatic reactions.

As used herein, a base-specifically terminated ribonucleotides is one that generated during transcription by incorporation a nucleotide that results in transcription termination. Base-specifically terminating ribonucleoside triphophates, which produce base-specifically terminated ribonucleotides, are known to those of skill in the art. Examples of base-specifically terminating ribonucleoside triphosphates include, but are not limited to: 3'-deoxyribonucleoside triphosphates, such as 3'-dGTP, and others described herein and known to those of skill in the art.

As used herein, complementary when referring to two nucleotide sequences, means that the two sequences of nucleotides are capable of hybridizing, preferably with less than 25%, more preferably with less than 15%, even more preferably with less than 5%, most preferably with no mismatches between opposed nucleotides. Preferably the two molecules will hybridize under conditions of high stringency.

As used herein: stringency of hybridization in determining percentage mismatch is as follows:

- 1) high stringency: 0.1 x SSPE, 0.1% SDS, 65°C
- 2) medium stringency: 0.2 x SSPE, 0.1% SDS, 50°C
- 3) low stringency: 1.0 x SSPE, 0.1% SDS, 50°C
- 20 It is understood that equivalent stringencies may be achieved using alternative buffers, salts and temperatures.

As used herein, the term "array" refers to an ordered arrangement of members or positions. The array may contain any number of members or positions and can be in any variety of shapes. In preferred embodiments, the array is two-dimensional and contains n x m members, wherein m and n are integers that can be the same or different. In particularly preferred embodiments, n and m are each 4 or a multiple thereof.

The term "cross-linking agent" is art-recognized, and, as used herein, refers to reagents taht immobilize a nucleic acid to an insolublesupport, preferably through covalent bonds. Thus, appropriate "crosslinking agents" for use herein includes a variety of agents that are 5 capable of reacting with a functional group present on a surface of the insoluble support and with a functional group present in the nucleic acid molecule. Reagents capable of such reactivity include homo- and heterobifunctional reagents, many of which are known in the art. Heterobifunctional reagents are preferred.

As used herein, the term "thiol-reactive functionality," refers to a functionality that reacts rapidly or preferably with a nucleophilic thiol moiety to produce a covalent bond, such as a disulfide or thioether bond. In general, thiol groups are good nucleophiles, and preferred thiol-reactive functionalities are reactive electrophiles. A variety of thiol-reactive 15 functionalities are known in the art, and include, for example, haloacetyls (preferably iodoacetyl), diazoketones, epoxy ketones, a,  $\beta$ -unsaturated carbonyls (such as, a,  $\beta$ -enones) and other reactive Michael acceptors (including maleimide), acid halides, benzyl halides, and the like. In certain embodiments, a free thiol group of a disulfide can react with a 20 free thiol group, such as by disulfide bond formation, including by disulfide exchange. A "thiol-reactive" cross-linking agent, as used herein, refers to a cross-linking reagent (or surface) which includes, or can be modified to include, at least one thiol-reactive functionality. Reaction of a thiol group can be temporarily prevented by blocking with 25 an appropriate protecting group, as is conventional in the art (see e.g.,

T.W. Greene and P.G.M. Wuts "Protective Groups in Organic Synthesis," 2nd ed. John Wiley & Sons, (1991)).

As used herein, a selectively cleavable linker is a linker that is cleaved under selected conditions, such as a photocleavable linker, a chemically cleavable linker and an enzymatically cleavable linker (i.e., a restriction endonuclease site or a ribonucleotide/RNase digestion). The linker is interposed between the support and immobilized DNA.

As used herein, the terms "protein", "polypeptide" and "peptide" are used interchangeably when referring to a translated nucleic acid, such as a gene product.

As used herein, "sample" refers to a composition containing a material to be detected. In a preferred embodiment, the sample is a "biological sample", which refers to any material obtained from a living source, including but not limited to animal, particularly mammals, including humans, plant, bacteria, fungi, protist and virus. The biological sample can be in any form, including solid materials, such as tissue, cells and biopsied material, and biological fluids, including urine, blood, saliva, amniotic fluid, cerebral spinal fluid and mouth wash (containing buccal cells). Preferably solid materials are mixed with a fluid.

As used herein, "substrate" or "solid support" shall mean an insoluble support onto which a sample is deposited according to the materials as described herein. Examples of appropriate substrates include beads, including but not limited to silica gel, controlled pore glass, magnetic, dextran, agarose and cellulose, capillaries, flat supports such as glass fiber filters, glass surfaces, metal surfaces (steel, gold, silver, aluminum, copper and silicon), plastic materials including multiwell plates or membranes (e.g., of polyethylene, polypropylene, polyamide, polyvinylidenedifluoride), pins, such as arrays of pins suitable for

combinatorial synthesis or analysis or beads in pits of flat surfaces such as wafers, pariticularly silicon wafers, with or without plates.

As used herein, RNA polymerase refers to DNA-dependent RNA polymerases and RNA-dependent RNA polymerases. Any RNA 5 polymerase that recognizes a specific promoter sequence and is capable of initiating transcription and elongating a RNA transcript is contemplated within the scope of the term herein. Exemplary RNA polymerases that may be used in the methods provided herein include, but are not limited to those obtained from: 1) archeabacteria, such as Halobacterium, 10 Methanobacterium, Methanococcus, Sulfolobales and Thermoplasma; 2) eubacteria, such as gram negative bacteria, e.g., Escherichia coli and strains of <u>Salmonella</u> and <u>Shigella</u>, gram positive bacteria, <u>e.g., Bacillus</u> subtilis and Staphlococcus aureus; 3) bacteriophages, such as T7, T3, SP6, SP6 nicked and N4; 4) DNA viruses; 5) RNA viruses, such as 15 influenza virus; 6) plants, such as wheat; and 7) eukaryotic RNA polymerase II isolated from fungii, s.g., Saccharomyces cerevisae and higher eukaryotic organisms, e.g., mammals. Also included within the scope of the term RNA polymerase as used herein is the RNA phage  $Q\beta$ replicase (see, e.g., International PCT application No.PCT/US87/00880 20 and 5,270,184). Eukaryotic RNA polymerases, such as those isolated from eukaryotic tissues, including plants and animals, that recognize eukaryotic promoters, including viral promoters from viruses that infect eukaryotic cells, are also contemplated herein. The T7, T3, and SP6 RNA polymerases have been cloned and their sequences and methods for 25 their purification as well as for purification of the bacterial RNA polymerases and certain eukaryotic DNA dependent RNA polymerases are known. In addition, numerous RNA polymerase commercially available in large quantities, and can also be readily produced from commerically available vectors. The sequences of the promoters for each

of the above-noted polymerases and other RNA polymerase are also known to those of skill in the art.

As used herein, a promoter region refers to the portion of DNA of a gene that controls expression of DNA to which it is operatively linked. 5 The promoter region includes specific sequences of DNA that are sufficient for RNA polymerase recognition, binding and transcription initiation. This portion of the promoter region is referred to as the promoter. In addition, the promoter region includes sequences that modulate this recognition, binding and transcription initiation activity of 10 the RNA polymerase. These sequences may be cis acting or may be responsive to trans acting factors. Promoters, depending upon the nature of the regulation, may be constitutive or regulated. A constitutive promoter is always turned on. A regulatable promoter requires specific signals to be turned on or off. A developmentally regulated promoter is 15 one that is turned on or off as a function of development. The promoter can be of a consensus sequence or variant. When a nonwild-type promoter is used, transcription will occur at a rate sufficient to produce a detectable transcript, and is typically at least about 5-10% of the rate at which transcription would have occurred if a wild-type or 20 native promoter had been used by the RNA polymerase to transcribe the nucleic acid in vitro. Each species of RNA polymerase is specific for a particular promoter sequence. Each of the three bacteriophage RNA polymerases (T7, T3, and SP6) has its own specific DNA promoter sequence. After the RNA polymerase has attached to the promoter 25 sequence of the template and transcription has been initiated, the promoter sequence releases the RNA polymerase. The RNA polymerase then continues transcription along the template until (1) it runs out of RNA starting materials, (2) the transcription reaction is terminated by a particular nucleotide, nucleoside or analog, (3) transcription is

spontaneously aborted when the RNA polymerase and the template prematurely disassociate or (4) the end of the DNA template is reached.

As used herein, a "promoter-containing nucleic acid" is a nucleic acid that contains a sequence of nucleotides that directs the site-specific 5 binding of an RNA polymerase molecule, which binds and melts the double-stranded DNA to form an open transcription initiation complex that is capable of initiating RNA synthesis in the presence of ribonucleotide triphosphates. Thus, a functional promoter sequence is a sequence of nucleotides to which a DNA dependent RNA polymerase 10 binds, melts in, forms an initiation complex and initiates transcription. The promoter-containing nucleic acid capture probe refers to the doublestranded molecule the includes the promoter region and a 3' overhang of at least about 5 nucleotides to which the target nucleic acid hybridizes, particularly under high stingency conditions. Typically such hybridization requires about 5 contiguous base pairs of identity between the target and promoter-containing capture probe. After initiating transcription, the RNA polymerase (or subunits thereof) is part of ternary complex containing the polymerase, the DNA, and the nascent RNA transcript.

As used herein, a "coding strand" refers to the nucleic acid strand
of a promoter-containing nucleic acid that has the same polarity as a
corresponding mRNA molecule initiated from that promoter. Thus, it
refers to the sense strand. The non-coding strand is the anti-sense
strand that is transcribed by RNA polymerase.

As used herein "native nucleoside (or ribonucleoside) triphosphate" or "native nucleotide" or ribonucleotide triphosphate means any one of the naturally occurring normal precursors of RNA, i.e., ATP, GTP, CTP, or UTP. A "nucleoside triphosphate analog" or "nucleotide analog" means any nucleoside triphosphate analogous to a native nucleotide, but that

contains one or more chemical modifications compared to the native nucleoside or nucleotide.

As used herein, a "matrix material" refers to a material used in mass spectrometry that is a proton donating, UV absorbing material, usually an organic acid, that forms crystalline matrix-nucleic acid structures that are readily ionizable during MALDI. An exemplary matrix material is a solution of 3-hydroxypicolinic acid (3-HPA, 0.7 M in 50% acetonitrile, 10% ammonium citrate).

As used herein, "conditioning" refers to a process whereby prior to mass spectrometric analysis, the nucleic acid to be analysed is modified, 10 for example to decrease the laser energy required for volatization and/or to minimize fragmentation. Conditioning can be performed on a nucleic acid, preferably after immobilization. An example of conditioning is modification of the phosphodiester backbone of the nucleic acid molecule 15 by, for example, cation exchange), eliminates peak broadening due to a heterogeneity in the cations bound per nucleotide unit. Contacting a nucleic acid molecule with an alkylating agent such as alkyliodide, iodoacetamide, -iodoethanol, or 2,3-epoxy-1-propanol, the monothio phosphodiester bonds of a nucleic acid molecule can be transformed into 20 a phosphotriester bond. Likewise, phosphodiester bonds may be transformed to uncharged derivatives employing trialkylsilyl chlorides. Conditioning also can be performed by incorporating modified nucleotides into a nucleic acid during synthesis. Such modified nucleatides can be used to reduce sensitivity for depurination (fragmentation during MS), sucg as with a purine analog such as N5-, N7- or N9-deazapurine nucleotides or ribonucleotide. Modified nucleotides also can include RNA building blocks, oligonucleotide triesters, phosphorothicate functions which are alkylated, or oligonucleotide mimetics such as PNA. In preparing conditioned RNA transcripts with modified nucleotides, the

RNA polymerase chosen must be able to incorporate the modified nucleotide into the RNA transcript.

#### Methods for sequencing

Mass spectrometric methods of sequencing nucleic acids are provided. In particular, the sequencing methods use nucleic acid promoter-containing probe that contain a double-stranded region encoding a promoter and a single-stranded region for hybridizing to a complementary region on target nucleic acids. The nucleic acid promoter-containing capture probe is preferably immobized on a solid support. The single-stranded region is hybridized to a complementary on a target nucleic acid, which contains the nucleic acid to be sequenced and at least 5 nucleotides of single-stranded region identical to the 5 contiguous single-stranded nucleotides on the probe.

Following hybridization of the target to the nucleic acid promoter-containing probes, the nucleic acid sequence is determined by generating a set of nested base-specific chain terminated RNA transcripts initiated from the promoter and transcribed through the target nucleic acid. The resulting nested RNA transcripts are analyzed using mass spectrometry.

While DNA is often the preferred vehicle for sequencing, the
methods herein are sequence RNA transcripts. RNA fragments are more
stable during matrix-assisted laser desorption/ionization (MALDI) mass
spectrometry than DNA fragments. Without being bound by any theory,
the enhanced stability may result from the presence of the 2'-hydroxyl
group on the sugar moiety of RNA, which helps to reduce depurination
during the MALDI process.

#### RNA polymerases and promoters

Any RNA polymerase capable of directing the in vitro transcription of an RNA molecule is contemplated for use in the methods described herein. Preferred RNA polymerases are DNA-dependent RNA 5 polymerases. Methods for isolating and purifying RNA polymerase molecules are well known to those of skill in the art: QB replicase (seee, e.g., U.S. Patent No. 5,696,249, Re: 35,443 and Eoyang et al. (1971) in Procedures in Nucleic Acid Research, Cantoni and Davies, eds., Volume 2, pp. 829-839, Harper and Rowe, NY); bacteria (e.g., E. coli, see 10 Burgess and Jendrisak (1975) Biochemistry 14:4634-4638 and Hager et <u>al.</u> (1990)<u>Biochemistrγ 29</u>:7890-7894; <u>Leishmania</u>, <u>e.g.</u>, see Sadhukhaπ et al. (1997) Mol. Cell. Biochem. 171:105-114; Bacillus subtilis, Giacomoni (1980) Eur. J. Biochem. 108:579-591); phage (e.g., T7, McDonnell et al. (1977) J. Mol. Biol. 89:719-736 and Studier et al. 15 (1969) Virology 39:562-574; see also He et al. (1997) Protein Expr. Purif. 9: 142-151); viruses (e.g., rhabdovirus, see Das et al. (1996) Methods Enzymol. 275:99-122; turnip mosiac virus, see Deidman et al. (1997) <u>J. Viral Meth.</u> 64:184-195; vaccīnia, Gershon et al. (1996) Methods Enzymol, 275:35-57); and mammalian (e.g., yeast polii, Koleske 20 et al. (1996) Methods Enzymol. 273:176-184; human polli, Maldonado et al. (1996) Methods Enzymol, 274:72-100). In addition, a number of prokaryotic, eukaryotic, bacteriophage and viral RNA polymerases, such as T3, T7 and SP6 are commercially available (e.g., sold by Stratagene, La Jolla, CA; Boehringer Mannheim, Indianapolis, IN; Pharmacia. Uppsala, 25 Sweden; and Sigma Chemical Corp, St. Louis, Mo) and/or well known. The promoters are also well known and readily available (e.g., the pGEM series of plasmids are available from Promega, Madison WI; see also, U.S. Patent No. 4,766,072, which describes construction of the pGEM plasmids).

25

In practicing the methods, DNA-dependent RNA polymerases and RNA-dependent RNA polymerases may be used. For example, RNA polymerases that may be used in the methods provided herein include, but are not limited to those obtained from: 1) archeabacteria, such as 5 Halobacterium, Methanobacterium, Methanococcus, Sulfolobales and Thermopiasma; 2) eubacteria, such as gram negative bacteria, e.g., Escherichia coli and strains of Salmonella and Shigella, gram positive bacteria, e.g., Bacillus subtilis and Staphlococcus aureus; 3) bacteriophages, such as T7, T3, SP6 and N4; 4) DNA viruses; 5) RNA 10 viruses, such as influenza virus; 6) plants and plant viruses, such as wheat and turnip mosiac virus; and 7) eukaryotic RNA polymerase II isolated from fungi, e.g., Saccharomyces cerevisae and higher eukaryotic organisms, e.g., mammals (e.g., for a review see in RNA Polymerase and the Regulation of Transcription, Rezinkoff at al., eds, Elsevier, NY). Also 15 included for use herein is the  $Q\beta$  replicase from the  $Q\beta$  RNA phage (e.g., see U.S. Patent Nos. 5,670,353, 5,696,249 and Re: 35,443).

The selection of the appropriate RNA polymerase for a nucleic acid template to be sequenced is within the skill of the skilled artisan and varies according to the nucleic acid molecule to be sequenced and the selected promoter region. The selection may be determined empirically following using teachings known to those of skill in the art, including those described herein. Preferred nucleic acid molecules to be sequenced are DNA molecules. RNA and, particularly, PNA (protein nucleic acids) are also amenable to sequencing, upon selection of an appropriate RNA polymerase.

Each nucleic acid promoter-containing probe used in the sequencing methods described herein contains a promoter. The promoters used in the methods herein can be obtained from any source or can be prepared synthetically based upon sequences recognized by

25

the selected RNA polymerase. For example, the nucleic acid containing a promoter may be obtained directly from a variety of different organisms, such as bacteria, viruses, phage and eukaryotic organisms, by cloning or may be obtained from commercially available expression vectors (e.g., 5 T7, T3, SP6 and  $A_{\rm PL}$  and  $A_{\rm PR}$  promoters from Boehringer Mannheim and Pharmacia; bla or lac promoters, RSV-LTR promoter and F9-1 promoter; Stratagene). The selection of the appropriate promoter will depend on the nucleic acid to be sequenced, sequencing conditions, and most importantly, on the RNA polymerase selected for transcription.

Promoters can be produced by hybridizing oligonucleotides encoding the coding and non-coding DNA strands of a promoter (see Example 4). The separate strands of nucleic acid are obtained preferably by nucleic acid synthetic techniques. Oligonucleotides used to assemble a promoter are designed such that following hybridization, there exists a 15 single stranded region at the 3'-end of the coding strand to which target DNA can hybridize.

## Immobilization of nucleic acid promoter-containing probes

In preferred embodiments, the nucleic acid promoter-containing probe is immobilized, directly or by means of a cross-linking agent, to a 20 solid support provided herein. The probe can be immobilized prior to hybridization or subsequent to hybridization to the target. Preferably and most conveniently hybridization is effected following immobilization to the solid support. The probe is preferably immobilized via the 5' end of the coding strand or the 3' end of the non-coding strand.

In other embodiments, a promoter and a downstream target nucleic acid can be isolated as a transcriptional unit from genomic DNA by amplification with primers or hybridization cloning technology. DNA encoding the promoter and target can then be immobilized onto a solid via the terminal nucleotides of the 5' end of the coding strand (sense

strand) or the 3'-end of the non-coding strand. As discussed further below, a linking group can be incorporated into PCR primers used to isolate the promoter-containing nucleic acid template to achieve directed immobilization to a support. Use of a suitable RNA polymerase that recognizes the promoter, will in the presence of chain terminating nucleotides will result in a set of nested fragments from which the sequence can be determined.

Preferred solid supports are those that can support linkage of nucleic acids thereto at high densities, preferably such that the 10 covalently bound nucleic acids are present on the substrate at a density of at least about 20 fmol/mm<sup>2</sup>, more preferably at least about 75 fmol/mm², still more preferably at least about 85 fmol/mm², yet more preferably at least about 100 fmol/mm<sup>2</sup>, and most preferably at least about 150 fmol/mm<sup>2</sup>. Among the most preferred substrates for use in the particular methods of immobilizing nucleic acids to substrates provided herein is silicon, whereas less preferred substrates include polymeric materials such as polyacrylamide. Substrates for use in methods of producing arrays provided herein include any of a wide variety of insoluble support materials including, but not limited to silica 20 gel, controlled pore glass, cellulose, glass fiber filters, glass surfaces, metal surfaces (steel, gold, silver, aluminum, silicon and copper), plastic materials (e.g., of polyethylene, polypropylene, polyamide, polyvinyldenedifluoride) and silicon.

In embodiments of the methods in which a cross-linking reagent is not employed, a modified nucleic acid is reacted directly with a appropriately functionalized surface to yield immobilized nucleic acid. Thus, for example, an iodoacetyl-modified surface (or other thiol-reactive surface functionality) can react with a thiol-modified nucleic acid to provide immobilized nucleic acids.

In embodiments using a cross-linking agent, the cross-linking agent is selected to provide a high density of nucleic acids immobilized on the insoluble support. The cross-linking agent (and other reagents used to functionalize the support surface or the nucleic acid molecule) can be selected to provide any desired spacing of the immobilized nucleic acid molecules from the support surface, and to provide any desired spacing of the immobilized nucleic acids from each other. Thus, steric encumbrance of the nucleic acid molecules can be reduced or eliminated by choice of an appropriate cross-linking agent. In certain embodiments, 10 the cross-linking reagent can be selected to provide multiple reactive functionalities as used in dendrimer synthesis for attachment of multiple nucleic acids to a single cross-linking moiety. Preferably, the crosslinking agent is selected to be highly reactive with the nucleic acid molecule, to provide rapid, complete, and/or selective reaction. In preferred embodiments, the reaction volume of the reagents (e,g), the thiol group reagent and the thiol-reactive functionality) is small.

## Modified nucleic acid promoter-containing probes and linkers

Preferred nucleic acid promoter-containing probes for use herein are "thiol-modified nucleic acids," i.e., nucleic acids derivatized to contain at least one reactive thiol moiety. As described in further detail in Example 1, below, nucleic acids containing at least one reactive thiol are preferably made by treating a nucleic acid containing a 3' or 5' disulfide with a reducing agent, which preferably will not compete in subsequent reactions (i.e. will not react with an iodoacetimido functionality). Disulfide-derivatized nucleic acids can be synthesized according to a variety of methods. For example, a nucleic acid can be modified at the 3'- or 5'-terminus by reaction with a disulfide-containing modifying a reagent. Alternatively, a thiolated primer can by enzymatically or non-enzymatically attached to the nucleic acid. A 5'-

phosphoramidate functionality can also provide an attachment point for a thiol or disulfide-containing cytosine or deoxycytosine. Examples of reducing agents appropriate for reduction of a disulfide-modified nucleic acid include: tris-(2-carboxyethyl)phosphine (TCEP) (preferably a 5 concentration in the range of 1-100 mM (most preferably about 10 mM)) is reacted at a pH in the range of 3-6 (most preferably about 4.5), a temperature in the range of 20-45°C (most preferably about 37°C) for a time period in the range of about 1 to about 10 hrs (most preferably for about 5 hrs); dithiothreitol (preferably a concentration in the range of 25 10 to 100 mM (depending on whether the reactant is isolated) is reacted at a pH in the range of 6-10 (most preferably about 8) and at a temperature in the range of 25-45°C (most preferably about 37°C)) for a time in the range of about 1 to about 10 hrs (most preferably about 5 hrs). TCEP provides an adventage in the low pH at which it is reactive. This low pH 15 effectively protonates thiols, thus suppressing nucleophilic reactions of thiols and resulting in fewer side reactions than with other disulfide reducing agents which are employed at higher pH.

As further described in Example 1, below, a preferred bifunctional cross-linking agent is N-succinimidyl(4-iodacetyl) aminobenzoate (SIAB).

20 Other crosslinking agents include, but are not limited to, dimaleimide, dithio-bis-nitrobenzoic acid (DTNB), N-succinimidyl-S-acetyl-thioacetate (SATA), N-succinimidyl-3-(2-pyridyldithiol propionate (SPDP), succinimidyl 4-(N-maleimidomethyl)cyclohexane-1-carboxylate (SMCC) and 6-hydrazinonicotimide (HYNIC) may also be used in the novel process. For further examples of cross-linking reagents, see, e.g., Wong "Chemistry of Protein Conjugation and Cross-Linking," CRC Press (1991), and Hermanson, "Bioconjugate Techniques" Academic Press (1995).

In other embodiments, the nucleic acid is immobilized using a photocleavable or photolabile linker moieties that is cleaved during mass spectrometry. Exemplary photolabile cross-linker include, but are not limited to, 3-amino-(2-nitrophenyl)propionic acid (Brown et al. (1995)

Molecular Diversity, pp.4-12 and Rothschild et al. (1996) Nucleic Acids Res. 24:361-66) See, also International PCT application No. (WO 98/20019).

A nucleic acid promoter-containing probe can be directly linked to a solid support via a reversible or irreversible bond between an appropriate functionality (L') on the target nucleic acid molecule (T) and an appropriate functionality (L) on the capture molecule. The format is similar to that shown in U.S. Patent No. 5,503,980. A reversible linkage includes linkages that are cleaved under the conditions of mass spectrometry. These include, but are not limited to photocleavable bonds, such as a charge transfer complex, and labile bonds formed between relatively stable organic radicals.

Furthermore, the linkage can be formed with L' being a quaternary ammonium group, in which case, the surface of the solid support, preferably, carries negative charges to repel the negatively charged nucleic acid backbone, thereby facilitating the desorption required for analysis by a mass spectrometer. Desorption can occur either by the heat created by the laser pulse and/or, depending on L,' by specific absorption of laser energy which is in resonance with the L' chromophore.

Thus, the L-L' chemistry can be of a type of disulfide bond (chemically cleavable, e.g., by mercaptoethanol or dithioerythrol; a biotin/streptavidin system; a heterobifunctional derivative of a trityl ether group; see, e.g., Köster et al. (1990) "A Versatile Acid-Labile Linker for Modification of Synthetic Biomolecules," <u>Tetrahedron Letters 31</u>:7095)

that can be cleaved under mildly acidic conditions as well as under conditions of mass spectrometry, a levulinyl group cleavable under almost neutral conditions with a hydrazinium/acetate buffer, an arginine-arginine or lysine-lysine bond cleavable by an endopeptidase enzyme like trypsin or a pyrophosphate bond cleavable by a pyrophosphatese, or a ribonucleotide bond in between the oligodeoxynucleotide sequence, which can be cleaved, for example, by a ribonuclease or alkali.

The functionalities, L and L,' can also form a charge transfer complex and thereby form the temporary L-L' linkage. Since in many cases the "charge-transfer band" can be determined by UV/vis spectrometry (see, e.g., Organic Charge Transfer Complexes by R. Foster, Academic Press, 1969), the laser energy can be tuned to the corresponding energy of the charge-transfer wavelength and, thus, a specific desorption off the solid support can be initiated. Those skilled in the art will recognize that several combinations can serve this purpose and that the donor functionality can be either on the solid support or coupled to the nucleic acid molecule to be detected or vice versa.

In another approach, a reversible L-L' linkage can be generated by homolytically forming relatively stable radicals. Under the influence of the laser pulse, desorption (as discussed above) as well as ionization will take place at the radical position. Those skilled in the art will recognize that other organic radicals can be selected and that, in relation to the dissociation energies needed to homolytically cleave the bond between them, a corresponding laser wavelength can be selected (see e.g., Reactive Molecules by C. Wentrup, John Wiley & Sons, 1984).

As noted, several embodiments of the method involving of immobilization are contemplated herein. These include, but are not limited to embodiments in which: 1) the primer nucleic acid is immobilized to the solid support and the target nucleic acid is hybridized

thereto to form a promoter sequence; 2) a double-stranded nucleic acid encoding a promoter (amplified or isofated) is immobilized through linkage to one predetermined strand, and in vitro transcription is initiated in the presence of a predetermined deoxy ribonucleotide, and 3) the target nucleic acid, which cam be amplified where there is available sequence information, is hybridized to a double-stranded nucleic acid capture probe with 3' overhang, and the resulting hybrids are immobilized.

In the embodiments where the primer nucleic acid is immobilized on the solid support and the target nucleic acid is hybridized thereto, the inclusion of a cleavable linker permits the primer DNA to be immobilized at the 5'-end so that free 3'-OH is available for "hybridizing" target DNA to the free DNA strand and initiating transcription to

Any linker known to those of skill in the art for immobilizing nucleic acids to solid supports may be used herein to link the nucleic acid to a solid support. The preferred linkers herein are the selectively cleavable linkers, particularly those exemplified herein. Other linkers include, acid cleavable linkers, such as bismaleimideothoxy propane and acid-labile trityl linkers. Acid cleavable linkers, photocleavable and heat sensitive linkers may also be used, particularly where it may be necessary to cleave the targeted agent to permit it to be more readily accessible to reaction.

#### Acid cleavable linkers

Acid cleavable linkers include, but are not limited to, bismaleimideothoxy propane; and adipic acid dihydrazide linkers (see, e.g., Fattom et al. (1992) Infection & Immun. 60:584-589) and acid labile transferrin conjugates that contain a sufficient portion of transferrin to permit entry into the intracellular transferrin cycling pathway (see, e.g., Walhöner et al. (1991) J. Biol. Chem. 266:4309-4314).

#### Photocleavable Linkers

Photocleavable linkers are linkers that are cleaved upon exposure to light (see, e.g., Goldmacher et al. (1992) Bioconj. Chem. 3:104-107), thereby releasing the targeted agent upon exposure to light. 5 Photocleavable linkers that are cleaved upon exposure to light are known (see, e.g., Hazum et al. (1981) in Pept., Proc. Eur. Pept. Symp., 16th, Brunfeldt, K (Ed), pp. 105-110, which describes the use of a nitrobenzyl group as a photocleavable protective group for cysteine; Yen et al. (1989) Makromol. Chem 190:69-82, which describes water soluble 10 photocleavable copolymers, including hydroxypropylmethacrylamide copalymer, glycine copolymer, fluorescein copalymer and methylrhodamine copolymer; Goldmacher et al. (1992) Bioconi. Chem. 3:104-107, which describes a cross-linker and reagent that undergoes photolytic degradation upon exposure to near UV light (350 nm); and Senter et al. (1985) Photochem. Photobiol 42:231-237, which describes nitrobenzyloxycarbonyl chloride cross linking reagents that produce photocleavable linkages), thereby releasing the targeted agent upon exposure to light. In preferred embodiments, the nucleic acid is immobilized using the photocleavable linker molety that is cleaved during 20 mass spectrometry.

#### Chemically cleavable linkers

A variety of chemically cleavable linkers may be used to introduce a cleavable bond between the immobilized nucleic acid and the solid support. Acid-labile linkers are presently preferred chemically cleavable linkers for mass spectrometry, especially MALDI-TOF MS, because the acid labile bond is cleaved during conditioning of the nucleic acid upon addition of the 3-HPA matrix solution. The acid labile bond can be introduced as a separate linker group, e.g., the acid labile trityl groups or may be incorporated in a synthetic nucleic acid linker by introducing one

or more silyl internucleoside bridges using diisopropylsilyl, thereby forming diisopropylsilyl-linked oligonucleotide analogs. The diisopropylsilyl bridge replaces the phoshodiester bond in the DNA backbone and under mildly acidic conditions, such as 1.5% trifluoroacetic acid (TFA) or 3-HPA/1% TFA MALDI-TOF matrix solution, results in the introduction of one or more intra-strand breaks in the DNA molecule. Methods for the preparation of diisopropylsilyl-linked oligonucleotide precursors and analogs are known to those of skill in the art (see e.g., Saha et al. (1993) J. Org. Chem. 58:7827-7831). These oligonucleotide analogs may be readily prepared using solid state oligonucleotide synthesis methods using diisopropylsilyl derivatized deoxyribonucleosides.

#### Modification of nucleic acids

### A. Mass modification

than the 3'- or 5'- terminus can be used. Modification of the sugar moiety of a nucleotide at positions other than the 3' and 5' position is possible through conventional methods. Also, nucleic acid bases can be modified, e.g., as described in F. Eckstein, ed., "Oligonucleotides and Analogues: A Practical Approach," IRL Press (1991). Such a linker arm can be modified to include a thiol moiety. Alternatively, backbonemodified nucleic acids can be used so that the thiol group can be attached to the nitrogen center provided by the modified phosphate backbone.

In preferred embodiments, modification of a nucleic acid, such as described above, does not substantially impair the ability of the nucleic acid molecule to hybridize to its complement. Thus, any modification should preferably avoid substantially modifying the functionalities of the nucleic acid that are responsible for Watson-Crick base pairing. The

20

nucleic acid can be modified such that a non-terminal thiol group is present, and the nucleic acid, when immobilized to the support, is capable of self-complementary base pairing to form a "hairpin" structure having a duplex region.

#### ₿. Other modifying RNA analogs

In practicing the methods described herein, a set (or sets) of nested base-specific chain terminated RNA transcripts is (are) generated during transcription by the incorporation of a modified base-specific chain terminating ribonucleotide analog (or specific cleavage by RNases in a 10 modified Maxam-Gilbert strategy). Any ribonucleoside triphosphate analog that results in the sequence-specific arrest of transcription elongation upon incorporation into an RNA molecule by an RNA polymerase may be used in the methods herein. Presently preferred ribonucleotide analogs are 3'-deoxyribonucleotides, result in basespecific termination of transcription (e.g., see Axelrod et al. (1985) Biochemistry 24:5716-5723; Tyagarajan et al. (1985) Biochemistry 30:10920-10924).

In certain embodiments, in addition to a base-specific chain terminating ribonucleoside triphosphate analog, additional ribonucleotide analogs can be added to reduce the secondary structure of the resulting RNA transcript and/or to prevent premature transcription termination or pausing or RNA cleavage. For example, the incorporation of riboinosine using inosine 5'-triphosphate is known to reduce the secondary structure of RNA products. In the presence of a dinucleotide guanine initiator, 25 inosine 5'-triphosphate can effectively substitute for GTP in in vitro transcription reactions (e.g., Axelrod et al. (1985) Biochemistry 24:5716-57231.

In addition, modified ribonucleotide analogs may be added to the transcription mixture to increase the efficiency of transcriptional

termination and/or transcript release to promote and facilitate the rate enzyme turnover. For example, the addition of 4-thio UTP, 5-bromo UTP, 5-iodo CTP alter the hydrogen bonding of the nucleic acid facilitating, at least with some RNA polymerases, transcriptional termination and 5 transcript release.

# Solld supports and substrates

Examples of insoluble supports and aubstrates for use herein include, but are not limited to: beads, such as silica gel, controlled pore glass, magnetic beads, dextran and agarose (Sephadex and Sepharose) 10 beads, cellulose beads and others, capillaries, flat supports such as glass fiber filters, glass surfaces, metal surfaces (steel, gold, silver, aluminum, silicon and copper), plastic materials including multiwell plates or membranes (e.g., of polyethylene, polypropylene, polyamide, polyvinyldenedifluoride), wafers, combs, pins (e.g., arrays of pins suitable for combinatorial synthesis or analysis) or beads in pits of flat surfaces such as wafers (e.g., silicon wafers), with or without filter plates.

#### Mass spectrometry

20

Once transcription is complete, the RNA transcripts can be analyzed by any of a variety of means including, for example, spectrometric techniques such as UV/VIS, IR, fluorescence, chemiluminescence, or NMR spectroscopy, mass spectrometry, gel electrophoresis and other methods known in the art, or combinations thereof. Mass spectrometry is preferred herein. Mass spectrometer 25 formats include the ionization (i) techniques, such as matrix assisted laser desorption (MALDI), continuous or pulsed electrospray (ESI) and related methods (e.g. lonspray or Thermospray), and massive cluster impact (MCI); these ion sources can be matched with detection formats including linear or reflectron time-of-flight (TOF), single or multiple

quadruple, single or multiple magnetic sector, Fourier Transform ion cyclotron resonance (FTICR), ion trap, and combinations thereof to yield a hybrid detector (e.g., ion-trap/time-of-flight). For ionization, numerous matrix/wavelength combinations (MALDI) or solvent combinations (ESI) 5 can be employed.

### Preparation of DNA arrays

summarized as follows.

15

In preferred embodiments, nucleic acid promoter-containing probes, prior to or subsequent to hybridization to target nucleic acids, are immobilized at to the surface of a solid support in an array format. 10 Particularly suitable methods for forming these DNA arrays are those described herein and U.S. application Serial Nos. 08/746,053, 08/787,639 and 08/786,988. The subject matter of each pending U.S. applications is herein incorporated by reference in its entirety and is

Figure 1 illustrates one system for preparing arrays of sample material for analysis by a diagnostic tool. Fig. 1 depicts a system 10 that includes a data processor 12, a motion controller 14, a robotic arm assembly 16, a monitor element 18A, a central processing unit 18B, a microliter plate of source material 20, a stage housing 22, a robotic arm 20 24, a stage 26, a pressure controller 28, a conduit 30, a mounting assembly 32, a pin assembly 38, and substrate elements 34. In the view shown by Fig. 1, it is also illustrated that the robotic assembly 16 can include a moveable mount element 40 and a horizontal slide groove 42. The robotic arm 24 can optionally pivot about a pin 36 to increase the 25 travel range of the arm 24 so that arm 24 can disposes the pin assembly 38 above the source plate 20.

The data processor 12 depicted in Fig. 1 can be a conventional digital data processing system such as an IBM PC compatible computer system that is suitable for processing data and for executing program

instructions that will provide information for controlling the movement and operation of the robotic assembly 16. The data processor unit 12 can be any type of system suitable for processing a program of instructions signals that will operate the robotic assembly that is 5 integrated into the robotic housing 16. Optionally the data processor 12 can be a micro-controlled assembly that is integrated into robotic housing 16. In further alternative embodiments, the system 10 need not be programmable and can be a single board computer having a firmware memory for storing instructions for operating the robotic assembly 16.

In the embodiment depicted in Fig. 1, there is a controller 14 that electronically couples between the data processor 12 and the robotic assembly 16. The depicted controller 14 is a motion controller that drives the motor elements of the robotic assembly 16 for positioning the robotic arm 24 at a selected location. Additionally, the controller 14 can 15 provide instructions to the robotic assembly 16 to direct the pressure controller 28 to control the volume of fluid ejected from the individual pin elements of the depicted pin assembly 38. The design and construction of the depicted motion controller 14 follows from principles well known in the art of electrical engineering, and any controller element suitable for 20 driving the robotic assembly 16 can be practiced without departing from the scope thereof.

The robotic assembly 16 depicted in Fig. 1 electronically couples to the controller 14. The depicted robotic assembly 16 is a gantry system that includes an XY table for moving the robotic arm about a XY plane, and further includes a Z axis actuator for moving the robotic arm orthogonally to that XY plane. The robotic assembly 16 depicted in Fig. 1 includes an arm 24 that mounts to the XY stage which moves the arm within a plane defined by the XY access. In the depicted embodiment, the XY table is mounted to the Z actuator to move the entire table along

the Z axis orthogonal to the XY plane. In this way, the robotic assembly provides three degrees of freedom that allows the pin assembly 38 to be disposed to any location above the substrates 34 and the source plate 20 which are shown in Fig. 1 as sitting on the stage 26 mounted to the robotic assembly 18.

The depicted robotic assembly 16 follows from principles well known in the art of electrical engineering and is just one example of a robotic assembly suitable for moving a pin assembly to locations adjacent a substrate and source plate such as the depicted substrate 34.

10 Accordingly, alternative robotic systems can be practiced following the descriptions herein without departing from the scope thereof.

Fig. 1 depicts an embodiment of a robotic assembly 16 that includes a pressure controller 28 that connects via a conduit 30 to the mount 32 that connects to the pin assembly 38. In this embodiment the mount 32 has an interior channel for fluidic coupling of the conduit 30 to the pin assembly 38. Accordingly, the pressure controller 28 is fluidicly coupled by the conduit 30 and the mount 32 to the pin assembly 38. In this way the controller 14 can send signals to the pressure controller 28 to control selectively a fluid pressure delivered to the pin assembly 38.

20

Fig. 2 depicts one embodiment of a pin assembly 50 suitable for practice with the system depicted in Fig. 1 which includes the pressure controller 28. In the depicted embodiment, the pin assembly 50 includes a housing formed from an upper portion 52 and a lower portion 54 that are joined together by the crews 56A and 56B to define an interior chamber volume 58. Fig. 2 further depicts that to fluidicly seal the interior chamber volume 58 the housing can include a seal element depicted in Fig. 2 as an O-ring gasket 60 that sites between the upper block and the lower block 54 and surrounds completely the perimeter of the interior chamber volume 58. Fig. 2 further depicts that the pin

assembly 50 includes a plurality of vesicles 62A-62D, each of which include an axial bore extending therethrough to form the depicted holding chambers 64A-64D. Each of the depicted vesicles extends through a respective aperture 68A-68D disposed within the lower block 54 of the bousing.

As further shown in the depicted embodiment, each of the vesicles 62A-62D has an upper flange portion that sits against a seal element 70A-70D to form a fluid-tight seal between the vesicle and the lower block 54 to prevent fluid from passing through the apertures 68A-68D. 10 To keep the seal tight, the depicted pin assembly 50 further includes a set of biasing elements 74A-74D depicted in Fig. 2 as springs which, in the depicted embodiments, are in a compressed state to force the flange element of the vesicles 62A-62D against their respective seal elements 70A-70D. As shown in Fig. 2, the biasing elements 74A-74D extend 15 between the vesicles and the upper block 52. Each of the springs 74A-74D can be fixedly mounted to a mounting pad 76A-76D where the spring elements can attach to the upper block 52. The upper block 52 further includes an aperture 78 depicted in Fig. 2 as a centrally disposed aperture that includes a threaded bore for receiving a swagelok 80 that can be rotatably mounted within the aperture 78. 20

As further depicted in Fig. 2, the swagelok 80 attaches by a conduit to a valve 82 than can connect the swagelok 80 to a conduit 84 that can be coupled to a pressure source, or alternatively can couple the swagelok 80 to a conduit 86 that provides for venting of the interior chamber 58. A central bore 88 extends through the swagelok 80 and couples to the tubing element which further connects to the valve 82 to thereby fluidicly and selectively couple the interior chamber volume 58 to either a pressure source, or a venting outlet.

25

The pin assembly 50 described above and depicted in Fig. 2 disposed above a substrate element 90 that includes a plurality of wells 92 that are etched into the upper surface of the substrate 90. As illustrated by Fig. 2, the pitch of the vesicles 62A-62D is such that each 5 vesicle is spaced from the adjacent vesicles by a distance that is an integral multiple of the pitch distance between wells 92 etched into the upper surface of the substrate 90. As will be seen from the following description, this spacing facilitates the parallel dispensing of fluid, such that fluid can be dispensed into a plurality of wells in a single operation. 10 Each of the vesicles can be made from stainless steel, silica, polymeric material or any other material suitable for holding fluid sample. In one example, 16 vesicles are employed in the assembly, which are made of hardened beryllium copper, gold plated over nickel plate. They are 43.2 mm long and the shaft of the vesicle is graduated to 0.46 mm outer 15 diameter with a concave tip. Such a pin was chosen since the pointing accuracy can be approximately 501 micrometers. Any suitable pin style can be employed for the device, including but not limited to flat, starshaped, concave, pointed solid, pointed semi-hollow, angled on one or both sides, or other such geometries.

Fig. 3 shows from a side perspective the lower block 54 of the pin assembly 50 depicted in Fig. 2. Fig. 3 shows approximate dimensions for one pin assembly. As shown, the lower block 54 has a bottom plate 98 and a surrounding shoulder 100. The bottom plate 98 is approximately 3 mm in thickness and the shoulder 100 is approximately 5 mm in thickness.

Fig. 4 shows from an overhead perspective the general structure and dimensions for one lower block 54 suitable for use with the pin assembly for use with the pin assembly 50 shown in Fig. 2. As shown in Fig. 4, the lower block 54 includes a four-by-four matrix of apertures

68 to provide 16 apertures each suitable for receiving a vesicle. As described above with reference to Fig. 2, the spacing between the aperture 68 is typically an integral multiple of the distance between wells on a substrate surface as well as the wells of a source plate.

5 Accordingly, a pin assembly having the lower block 54 as depicted in Fig. 4 can dispense fluid in up to 16 wells simultaneously. Fig. 4 also shows general dimensions of one lower block 54 such that each side of block 54 is generally 22 mm in length and the pitch between aperture 68 is approximately 4.5 mm. Such a pitch is suitable for use with a substrate where fluid is to be dispensed at locations approximately 500 µm apart, as exemplified by the substrate 90 of Fig. 2. Fig. 4 also shows that the lower block 54 can include an optional O-ring groove 94 adapted for receiving an O-ring seal element, such as the seal element 60 depicted in Fig. 2. It is understood that such a groove element 94 can enhance and improve the fluid seal formed by the seal element 60.

The pinblock can be manufactured of stainless steel as this material can be drilled accurately to about +25 µm, but a variety of probe materials can also be used, such as G10 laminate, PMMA or other suitable material. The pin block can contain any number of apertures and is shown with 16 receptacles which hold the 16 pins in place. To increase the pointing accuracy of each pin, an optional alignment place can be placed below the block so that about 6 mm of the pin tip is left exposed to enable dipping into the wells of a microtiter plate. The layout of the probes in the depicted tool is designed to coordinate with a 384-well microtiter plate, thus the center-to-center spacing of the probes in 4.5 mm. An array of 4 x 4 probes was chosen since it would produce an array that would fit in less than one square inch, which is the travel range of an xy stage of a MALDI TOF MS employed by the assignee.

The pintool assembly is completed with a stainless steel cover on the top side of the device which is then attached onto the Z-arm of the robot.

With reference to Figs 1 and 2, the robotic assembly 16 employs a pin tool assembly 38 that is configured similarly as the pin tool assembly 50 depicted in Figure 2. The pressure controller 28 selectively controls the pressure within chamber 58. With this embodiment, a control program operates on the data processor 12 to control the robotic assembly 16 in a way that the assembly 16 prints an array of elements on the substrates 34. In a first step, (see, also Figures 2 and 5), the 10 program directs the robotic assembly 16 to move the pin assembly 38 to be disposed above the source plate 20. The robotic assembly 16 will then dip the pin assembly into the source plate 20 which can be a 384 well DNA source plate. As shown in Fig. 4 the pin assembly can include 16 different pins such that the pin assembly 50 will dip 16 pins into different 16 wells of the 384 well DNA source plate 20. Next the data processor 12 will direct the motion controller 14 to operate the robotic assembly 16 to move the pin assembly to a position above the surface of the substrate 34. The substrate 34 can be any substrate suitable for receiving a sample of material and can be formed of silicon, plastic, 20 metal, or any other such suitable material. Optionally the substrate will have a flat surface, but can alternatively include a pitted surface, a surface etched with wells or any other suitable surface typography and further containing beads on the surface of each well. The program operating on data processor 12 can then direct the robotic assembly, 25 through the motion controller 14, to direct the pressure controller 28 to generate a positive pressure within the interior chamber volume 58. In this practice, the positive interior pressure will force fluid from the holding chambers of vesicles 62 to eject fluid from the vesicles and into a respective well 92 of the substrate 90.

The program operating on data processor 12 can also direct the controller 14 to control the pressure controller 28 to control filling the holding chambers with source material from the source plate 20. The pressure controller 28 can generate a negative pressure within the interior chamber volume 58 of the pin assembly. This will cause fluid to be drawn up into the holding chambers of the vesicles 62A-62D. The pressure controller 28 can regulate the pressure either by open-loop or closed-loop control to avoid having fluid overdrawn through the holding chambers and spilled into the interior chamber volume 58. Loop control systems for controlling pressure are well known in the art and any suitable controller can be employed. Such spillage could cause cross-contamination, particularly if the source material drawn from the source plate 20 varies from well to well.

In an alternative embodiment, each of the holding chambers 64A15 64D is sufficiently small to allow the chambers to be filled by capillary action. In such a practice, the pin assembly can include an array of narrow bore needles, such as stainless steel needles, that extend through the apertures of the lower block 54. The needles that are dipped into source solutions will be filled by capillary action. In one practice, the
20 length of capillary which is to be filled at atmospheric pressure is determined approximately by:

H = <u>2γ</u> PGF

where H equals Height, gamma equals surface tension, P equals solution density, G equals gravitational force and R equals needle radius. Thus the volume of fluid held by each vesicle can be controlled by selecting the dimensions of the interior bore. It is understood that at room temperature water will fill a 15 cm length of 100 µm radius capillary. Thus, a short bore nanoliter volume needle will fill to full capacity, but should not overflow because the capillary force is understood to be too

small to form a meniscus at the top of the needle orifice. This prevents cross-contamination due to spillage. In one embodiment, the vesicles of the pin assembly can be provided with different sized interior chambers for holding and dispensing different volumes of fluid.

In an alternative practice, to decrease the volume of liquid that is drawn into the holding chambers of the vesicles, a small positive pressure can be provided within the interior chamber volume 58 by the pressure controller 28. The downward force created by the positive pressure can be used to counter the upward capillary force. In this way, 10 the volume of fluid that is drawn by capillary force into the holding chambers of the vesicles can be controlled.

Fig. 5B shows that fluid within the holding chambers of the needle can be dispensed by a small positive pressure introduced through the central bore 88 extending through a swagelok 80. By regulating the 15 pressure pulse that is introduced into the interior chamber volume 58, fluid can be ejected either as a spray or by droplet formation at the needle tip. It is understood that the rate of dispensing, droplet versus spray, depends in part upon the pressure applied by the pressure controller 28. In one practice, pressure is applied in the range of 20 between 10 and 1,000 Torr of atmospheric pressure.

To this end the data processor 12 can run a computer program that controls and regulates the volume of fluid dispensed. The program can direct the controller 28 to eject a defined volume of fluid, either by generating a spray or by forming a drop that sits at the end of the vesicle, and can be contacted with the substrate surface for dispensing the fluid thereto.

Figures 5C and 5D show the earlier steps shown in Figs. 5A-5B can again be performed, this time at a position on the substrate surface that is offset from the earlier position. In the depicted process, the pin

WO 99/31278 PCT/US98/26718

-46-

tool is offset by a distance equal to the distance between two wells 92. Other offset printing techniques can be employed.

Several advantages of the pin assembly depicted in Fig. 2 are achieved. For example, rinsing between dispensing events is straightforward, requiring only single or multiple pin fillings and emptying events with a rinse solution. Moreover, since all holding chambers fill to full capacity, the accuracy of the volumes dispensed varies only according to needle inner dimensions which can be carefully controlled during pin production. Further the device is cost effective, with the greatest expense attributed to the needles, however because no contact with a surface is required, the needles are exposed to little physical strain or stress, making replacement rare and providing long life.

Alternatively, deposition of sample material onto solid support surface can include techniques that employ pin tool assemblies that have solid pin elements extending from a block wherein a robotic assembly dips the solid pin elements of the pin assembly into a source of sample material to wet the distal ends of the pins with the sample materials. Subsequently the robotic assembly can move the pin assembly to a location above the substrate and then lower the pin assembly against the surface of the substrate to contact the individual wetted pins against the surface for spotting material of the substrate surface.

Pin tool assemblies that have solid pins with a promoter-containing nucleic acid immobilized thereon can be dipped into wells containing a reaction mixture for hybridization and/or generation of RNA transcript. The liquid with the transcripts can then be deposited in an array as discussed above, for example by using solid pins of a pin tool assembly to spot sample on the substrate surface.

Figures 6A and 6B depict another alternative system for dispensing material on or to the surface of the substrate. In particular, Figure 6A

depicts a jet printing device 110 which includes a capillary element 112, a transducer element 114 and orifice (not shown) 118, a fluid conduit 122, and a mount 124 connecting to a robotic arm assembly, such as the robotic arm 24 depicted in Figure 1. As further shown in Figure 6A 5 the jet assembly 110 is suitable for ejecting from the orifice 118 a series of drops 120 of a sample material for dispensing sample material onto the surface 128.

The capillary 112 of the jet assembly 110 can be a glass capillary. a plastic capillary, or any other suitable housing that can carry a fluid 10 sample and that will allow the fluid sample to be ejected by the action of a transducer element, such as the transducer element 114. The transducer element 114 depicted in Figure 6A is a piezo electric transducer element which forms around the parameter of the capillary 112 and can transform an electrical pulse received from the pulse 15 generator within a robotic assembly 16 to cause fluid to eject from the orifice 118 of the capillary 112. One such jet assembly having a piezgelectric transducer element is manufactured by MicroFab Technology, Inc., of Germany. Any jet assembly, however, that is suitable for dispensing defined and controlled the volumes of fluid can be used herein including those that use piezoelectric transducers, electric transducers, electrorestrictive transducers, magnetorestrictive transducers, electromechanical transducers, or any other suitable transducer element. In the depicted embodiment, the capillary 112 has a fluid conduit 122 for receiving fluid material. In an optional embodiment, 25 fluid can be drawn into the capillary by action of a vacuum pressure that will draw fluid through the orifice 118 when the orifice 118 is submerged in a source of fluid material. Other embodiments of the jet assembly 110 can be practiced with the invention without departing from the scope thereof.

Figure 6B illustrates a further alternative assembly suitable for p being carried on the robotic arm of a robotic assembly, such as the assembly 16 depicted in Figure 1. Figure 6B illustrates four jet assemblies connected together, 130A-130D. Similar to the pin assembly 5 in Figure 2, the jet assembly depicted in Figure 6B can be employed for the parallel dispensing of fluid material. Each of the jet assemblies 130A-130D can be operated independently of the others, allowing the selective dispensing of fluid from select ones of the jet assemblies. Moreover, each of the jet assemblies 130A-130D can be independently controlled to 10 select the volume of fluid that is dispensed from each respected one of the assembly 130A-130D. Other modifications and alterations can be made to the assembly depicted in Figure 6B without departing from the scope of the invention.

Arrays can be formed on a substrate surface according to any of the techniques discussed above. The sample arrays are then analyzed by mass spectrometry to collect spectra data that is representative of the composition of the samples in the array. It is understood that the above methods provide processes that allow for rapidly dispensing definite and controlled volumes of analyte material. In particular these processes 20 allow for dispensing sub to low nanoliter volumes of fluid. These low volume deposition techniques generate sample arrays well suited for analysis by mass spectrometry. For example, the low volumes yield reproducibility of spot characteristics, such as evaporation rates and reduced dependence on atmospheric conditions such as ambient temperature and light.

Continuing with the example shown in Fig. 5, the arrays can be prepared by loading oligonucleotides (0.1-50  $ng/\mu$ l) of different sequences or concentrations into the wells of a 96 well microtiter source plate 20; the first well can be reserved for holding a matrix solution. A

25

substrate 34, such as a pitted silicon chip substrate, can be placed on the stage 26 of the robotics assembly 16 and can be aligned manually to orient the matrix of wells about a set of reference axes. The control program executing on the data processor 12 can receive the coordinates 5 of the first well of the source plate 20. The robotic arm 24 can dip the pin assembly 38 into source plate 20 such that each of the 16 pins is dipped into one of the wells. Each vesicle can fill by capillary action so that the full volume of the holding chamber contains fluid. Optionally, the program executing on the data processor 12 can direct the pressure 10 controller to fill the interior chamber 58 of the pin assembly 38 with a positive bias pressure that will counteract, in part, the force of the capillary action to limit or reduce the volume of fluid that is drawn into the holding chamber,

Optionally, the pin assembly 38 can be dipped into the same 16 wells of the source plate 20 and spotted on a second target substrate. This cycle can be repeated on as many target substrates as desired. Next the robotic arm 24 can dip the pin assembly 38 in a washing solution, and then dip the pin assembly into 16 different wells of the source plate 20, and spot onto the substrate target offset a distance 20 from the initial set of 16 spots. Again this can be repeated for as many target substrates as desired. The entire cycle can be repeated to make a 2x2 array from each vesicle to produce an 8x8 array of spots (2x2 elements/vesicle x 16 vesicles = 64 total elements spotted). Any process suitable for forming arrays can be employed.

Oligonucleotides of different sequences or concentrations can be loaded into the wells of up to three different 384-well microtiter source plates; one set of 16 wells can be reserved for matrix solution. The wells of two plates are filled with washing solution. Five microtiter plates can be loaded onto the stage of the robotic assembly 16. A

plurality of target substrates can be placed abutting an optional set of banking or registration pins disposed on the stage 26 and provided for aligning the target substrates along a set of reference axes. If the matrix and oligonucleotide are not pre-mixed, the pin assembly can be employed to first spot matrix solution on all desired target substrates. In a subsequent step the oligonucleotide solution can be spotted in the same pattern as the matrix material to re-dissolve the matrix. Alternatively, a sample array can be made by placing the oligonucleotide solution on the wafer first, followed by the matrix solution, or by pre-mixing the matrix and oligonucleotide solutions.

After depositing the sample arrays onto the surface of the substrate, the arrays can be analyzed using any of a variety of means '(e.g., spectrometric techniques, such as UV/VIS, IR, fluorescence, chemiluminescence, NMR spectrometry or mass spectrometry. For example, subsequent to either dispensing process, sample loaded substrates can be placed onto a MALDI-TOF source plate and held there with a set of beveled screw mounted polycarbonate supports. In one practice, the plate can be transferred on the end of a probe to be held onto a 1µm resolution, 1" travel xy stage (Newport) in the source region of a time-of-flight mass spectrometer. Any suitable mass spectrometry tool can be employed.

Preferred mass spectrometer formats for use with the arrays described herein include ionization (I) techniques including but not limited to matrix assisted laser desorption (MALDI), continuous or pulsed electrospray (ESI) and related methods (e.g. lonspray or Thermospray), or massive cluster impact (MCI); those ion sources can be matched with detection formats including linear or non-linear reflectron time-of-flight (TOF), single or multiple quadruple, single or multiple magnetic sector, Fourier Transform ion cyclotron resonance (FTICR), ion trap, and

W() 99/31278 PCT/US98/26718

-51-

combinations thereof (e.g., ion-trap/time-of-flight). For ionization, numerous matrix/wavelength combinations (MALDI) or solvent combinations (ESI) can be employed. Subattomole levels of protein have been detected for example, using ESI (Valaskovic, G. A. et al., {1996})

5 Science 273: 1199-1202) or MALDI (Li, L. et al., (1996) J. Am. Chem. Soc 118: 1662-1663) mass spectrometry.

Thus, it will be understood that in processes described herein a completely non-contact, high-pressure spray or partial-contact, low pressure droplet formation mode can be employed. In the latter, the only contact that will occur is between the droplet and the walls of the well or a hydrophilic flat surface of the substrate 34. In neither practice need there be any contact between the needle tip and the surface.

#### Exemplary embodiment

In one preferred embodiment, a double-stranded nucleic acid
sequence encoding a promoter sequence is isolated from a natural source
(e.g., bacteria, viruses, bacteriophages, plants or eukaryotic organisms)
or assembled from synthetic sequences. A single-stranded region of at
least a 5 nucleotides at the 3'-end of the coding strand using standard
methods known to those of skill in the art (e.g., see Sambrook et al.,
(1989) Molecular Cloning, 2nd ed., Cold Spring Harbor Laboratory Press,
New York). This single-stranded region is designed such that it is
complementary to a region of the nucleic acid to be sequenced or to an
sequence shared between the two nucleic acid molecules (e.g., a
restriction endonuclease site).

The nucleic acid to be sequenced containing at least a partially single-stranded 3'-end is hybridized according to the conditions described herein, preferably high stringency such that 5 contiguous matching base pairs form, and known to those of skill in the art to the complementary sequences of the promoter-containing DNA. The nucleic acid to be

sequenced may be double-stranded or preferably single-stranded. The hybridization of the two nucleic acid molecules introduces one or more "nicks" in the hybrid at the junction(s) of the adjacent nucleic acid molecules. Nicks in the coding or non-coding strand, preferably the 5 coding strand, can be ligated by the addition of an appropriate nucleic acid ligase prior to initiating transcription. Methods for ligating nucleic acids are well known to those of skill in the art (e.g., see Sambrook et al., (1989) Molecular Cloning, 2nd ed., Cold Spring Harbor Laboratory Press, New York) and DNA and RNA ligases are commercially available (e.g., Boehringer Mannheim, Indianapolis, IN).

Transcription is initiated from the promoter by the addition of the appropriate RNA polymerase in the presence of ribonucleoside triphosphates under conditions described herein and known elsewhere (e.g., In RNA Polymerase and the Regulation of Transcription, Rezinkoff 15 et al., eds. Elsevier, NY). In preferred embodiments, a selected basespecific chain terminating 3'-deoxyribonucleoside triphosphate and the transcription mixture also contains inosine 5'-triphosphate to reduce the secondary structure of the RNA product or modified ribonucleoside triphosphates, such as 4-thio UTP, 5-bromo UTP or 5'-iodo CTP to 20 facilitate turnover of the RNA polymerase enzyme and thereby increase the amount of RNA transcript available for analysis.

In preferred embodiments, the nucleic acid promoter-containing probe is covalently immobilized on a silica support by functionalization of the support with an amino functionality (e.g., by derivatization of the 25 support with a reagent such as 3-aminopropyl-triethoxysilane (Aldrich Chemical Co., Milwaukee, WI); see Figure 7). Other functionalized oxysilanes or orthosilicates can be used, and are commercially available (e.g., from Gelest, Inc., Tullytown, PA). For example, 3-mercaptopropyltriethoxysilane can be used to functionalize a silicon surface with thiol

groups. The amino-functionalized silica can then be reacted with a heterobifunctional reagent such as N-succinimidyl (4-iodacetyl) aminobenzoate (SIAB) (Pierce, Rockford, IL). Other homo- and heterobifunctional reagents which can be amployed are available commercially, e.g., from Pierce. Finally, a nucleic acid functionalized with a thiol group (e.g., at the 5'-terminus) is covalently bound to the derivatized silica support by reaction of the thiol functionality of the nucleic acid molecule with the iodoacetyl functionality of the support.

In certain embodiments, the nucleic acid can be reacted with the cross-linking reagent to form a cross-linker/nucleic acid conjugate, which is then reacted with a functionalized support to provide an immobilized nucleic acid. Alternatively, the cross-linker can be combined with the nucleic acid and a functionalized solid support in one pot to provide substantially simultaneous reaction of the cross-linking reagent with the nucleic acid and the solid support. In this embodiment, it will generally be necessary to use a heterobifunctional cross-linker, i.e., a cross-linker with two different reactive functionalities capable of selective reaction with each of the nucleic acid and the functionalized solid support.

arrays of nucleic acids immobilized on insoluble supports that are suitable for sequencing of nucleic acids using RNA polymerase can be prepared. For example, the methods can be used to provide arrays of different nucleic acids immobilized on pins arranged in an array. In another embodiment, a photo-cleavable protecting group on the insoluble support can be selectively cleaved (e.g., by photolithography) to provide portions of a surface activated for immobilization of a nucleic acid. For example, a silicon surface, modified by treatment with 3-mercaptopropyl-triethoxysilane to provide thiol groups, can be blocked with a photocleavable protecting group (for examples of photocleavable)

protecting groups, see, e.g., PCT Publication WO 92/10092, or McCray et al.. (1989) Ann. Rev. Biophys. Biophys. Chem. 18:239-270), and be selectively deblocked by irradiation of selected areas of the surface, e.g., by use of a photolithography mask. A nucleic acid promoter-containing 5 probe modified to contain a thiol-reactive group can then be attached directly to the support, or, alternatively, a thiol-reactive cross-linking reagent can be reacted with the thiol-modified support, followed by (or substantially simultaneously with) reaction with a nucleic acid to provide immobilized nucleic acids. A nucleic acid base or sequence, once 10 immobilized on a support according to the methods described herein, can be further modified according to known methods. For example, the nucleic acid molecule can be lengthened by performing solid-phase nucleic acid synthesis according to conventional techniques, including combinatorial technique

Preferably the nucleic acids are cavalently bound to a surface of the insoluble support through at least one sulfur atom, i.e., the nucleic acids are covalently bound to the surface through a linker moiety which includes at least one sulfur atom. Such covalently bound nucleic acids are readily produced by the methods described herein. In preferred 20 embodiments, the covalently bound nucleic acids are a present on the surface of the insoluble support at a density of at least about 20 fmol/mm2, more preferably at least about 75 fmol/mm2, still more preferably at least about fmol/mm2, yet more preferably at least about 100 fmol/mm<sup>2</sup>, and most preferably at least about 150 fmol/mm<sup>2</sup>.

#### 25 Applications

15

The methods of sequencing nucleic acids described herein may be used for a variety of end use applications. For example, the methods may be used for diagnostic applications for the identification of mutations, such as transitions, transversions, deletions, insertions and

25

the like. The methods may also be used to assist in the diagnosis of a number of genetic disorders, used for genetic screening or the determination of heredity or tissue or organ compatibility.

The method of sequencing may be used for diagnostic applications 5 to determined the presence of genetic alterations in a known target nucleic acid. For example, a region of the target nucleic acid can be amplified using standard methods, such as PCR or other amplification methods known to those of skill in the art (<u>e.g.</u>,see Sambrook <u>et al.,</u> (1989) Molecular Cloning, 2nd ed., Cold Spring Harbor Laboratory Press, 10 New York). The amplified nucleic acid can be denaturated and the strand to be sequenced (the noncoding strand, is isolated or may be used as a double-stranded molecule.

The presence of genetic alterations in a known target nucleic is determined in a diagnostic application by isolating (or amplifying) a target nucleic acid from a biological sample and hybridizing the target to a promoter containing capture probe to generate a promoter containing template. A nested set of RNA transcripts is generated and the sequence of the target nucleic acid determined and compared with a wildtype sequence to determine if a genetic alteration has occurred in the 20 target nucleic acid. The presence of a genetic alteration can be determined from the RNA transcripts by other means known in the art (see, e.g., U.S. Patent No. 5,605,798 and International PCT application No. WO 98/200191.

# Methods of Identifying Transcriptional Terminator Sequences

Methods of identifying heretofore unknown transcriptional terminator and attenuator sequences are also provided. Transcriptional terminator sequences are responsible for the sequence specific cessation of RNA elongation and such terminator sequences from a variety of organisms have been reported. For example, bacterial rho-independent

terminator sequences have two inverted repeats separate by several base pairs followed by a 5-10 nt polyT stretch. Upon transcription through these sequences, the resulting mRNA transcript forms a RNA hairpin stem-loop secondary structure behind the RNA polymerase molecule that increases pausing of RNA polymerase and/or destabilizes the RNA polymerase-DNA template interaction resulting in termination of the transcript within the DNA polyT stretch. (e.g., see Wilson and von Hippel (19; Reynolds et al. (1992a) J. Mol. Biol. 224:53-63; Reynolds et al. (1992b) J. Mol. Biol. 224:31-51; Telesnitsky et al. (1989) Biochemistry 28:5210-5218; d'Aubenton Carafa et al. (1990) J. Mol. Biol. 216:835-858).

Bacterial rho-dependent terminators lack the traditional inverted repeat stem-loop structure and further require additional factors, such as rho protein, to halt transcription (e.g., see Schmidt et al. (1984) J. Mol. Biol. 259:15000-15002). Rho-dependent termination is believed to result in the premature termination in bacterial species upon uncoupling of transcription and translation.

herein, transcriptional terminator sequences, e.g., rho-dependent and rhoindependent terminators, may be identified using mass spectrometric methods. In practicing the methods, a single-stranded region of the 3'end of the nucleic acid to be sequenced is hybridized to a complementary sequence at the 3'-end of the coding strand a promoter-containing nucleic acid probe. In preferred embodiments, the promoter-containing nucleic acid is covalently coupled via the 5'-end of the noncoding strand or 3'-end of the coding strand to a solid support and, more preferably, is a 5'- or 3'-thiolated DNA linked at high densities to a aminosilane-treated solid support. The linkage may be in the absence or presence of a linker group and is preferably arranged in an array format.

15

Transcription is initiated in the absence or presence of modified RNA triphosphate analogs that increase the efficiency of RNA polymerase termination at such terminator sequences, such as 4-thio UTP, 5-bromo UTP or 5'-lodo CTP. The mass of the specifically terminated RNA 5 transcripts can be detected by mass spectrometry where the observed mass of the RNA is indicative of the location of the terminator-dependent arrest of transcription. By comparing of the alignment of the sequence immediately preceding the site of transcriptional termination from several distinct genomic locations, heretofore unknown terminator sequences may be identified for different RNA polymerases.

In certain embodiments, nicks in one or more strand resulting from the hybridization of the nucleic acid to be sequenced may be ligated by the addition of an appropriate nucleic acid ligase prior to initiating transcription (i.e., adding a DNA or RNA ligase).

The present invention is further illustrated by the following Examples, which area intended merely to further illustrate and should not be construed as limiting. The entire contents of all the of the references (including literature references, issued patents, published patent applications, and co-pending patent applications) cited throughout this application are hereby expressly incorporated by reference.

## **EXAMPLE 1**

# High Density Attachment of nucleic Acids to Silicon Wafers Materials and Methods

All reagents, unless otherwise noted, were obtained from Aldrich 25 Chemical, Milwaukee, WI.

#### Silicon Surface Preparation

Silicon wafers were washed with ethanol, flamed over bunsen burner, and immersed in an anhydrous solution of 25% (by volume) 3-aminopropyltriethoxysilane in toluene for 3 hours. The silane solution was then removed, and the wafers were washed three times with toluene and three times with dimethyl sulfoxide (DMSO). The wafers were then incubated in a 10 mM anhydrous solution of N-succinimidyl (4-iodoacetyl) aminobenzoate (SIAB) (Pierce Chemical, Rockford, IL) in anhydrous DMSO. Following the reaction, the SIAB solution was removed, and the wafers were washed three times with DMSO.

Since it was impossible to monitor the condensation of SIAB and the amino group while on the solid support of the wafer, the reaction was performed in solution to determine the optimal reaction time. Thin layer chromatography (TLC) (glass backed silica plates with a 254 nm fluorescent indicator) (Baker, Phillipsburg, NF) was employed using 95:5 chloroform:methanol (Baker, Phillipsburg, NJ) which enabled separation of the two starting materials. It was possible to visualize the SIAB starting material under long wave ultraviolet light (302 nm): 3-aminopropyltriethoxysilane was not active under ultraviolet light, therefore, the plate was sprayed with a solution of ninhydrin which reacts with primary amines to reveal a purple spot upon heating. A microscale reaction was run in chloroform/DMSO using a slight molar excess of SIAB in comparison to 3-aminopropyltriethoxysilane and monitored with the above mentioned TLC conditions.

## Oligonucleotide Modifications

25

Reduction of the disulfide from 3'- or 5'-disulfide-containing oligodeoxynucleotides (Operon Technologies, Alameda, CA or Oligo Etc., Wilsonville, OR) was monitored using reverse-phase FPLC (Pharmacia, Piscataway, NJ); a shift can b seen in the retention time of the

oligodeoxynucleotide upon cleavage of the disulfide. Various reduction methods were investigated to determine the optimal conditions. In one case, the disulfide-containing oligodeoxynucleotide (31.5 nmol, 0.5 mM) was incubated with dithiothreitol (DTT) (Pierce Chemical, Rockford, IL) 5 (8.2 mmol, 100 mM) as pH 8.0 and 37°C. With the cleavage reaction essentially complete, the free thiol-containing oligodeoxynucleotide was isolated using a Chromaspin-10 column (Clontech, Palo Alto, CA) since DTT may compete in the subsequent reaction. Alternatively, tris-(2carboxyethyl) phosphine (TCEP) (Pierce Chemical, Rockford, IL) has been 10 used to cleave the disulfide. The disulfide-containing oligodeoxynucleotide (7.2 nmol, 0.36 mM) was incubated with TCEP in pH 4.5 buffer at 37°C. It is not necessary to isolate the product following the reaction since TCEP does not competitively react with the iodoacetamido functionality. Varying concentrations of TCEP were used for the cleavage reaction to determine the optimal conditions for the conjugation reaction.

#### **Probe Coupling**

To each wafer which had been derivatized to contain the iodoacetamido functionality as described above was added a 10 mM aqueous solution of the free-thiol containing oligodeoxynucleotide in 100 mM phosphate buffer, pH 8; the reaction was allowed to proceed for a minimum of five hours at room temperature in 100% relative humidity. Following the reaction, the oligodeoxynucleotide solution was removed, and the wafers were washed two times in 5 X SSC buffer (75 mM sodium citrate, 750 mM sodium chloride, pH 7) with 50% formamide (USB, Cleveland, OH) at 65°C for 1 hour each.

# Radiochemical Determination of Probe Density

In order to determine the amount of DNA covalently attached to a surface or the amount of a complementary sequence hybridized, radiolabeled probes were employed. In cases where a 5'-disulfide-5 containing oligodeoxynucleotide was to be immobilized, the 3'-terminus was radiolabeled using terminal transferase enzyme and a radiolabeled dideoxynucleoside triphosphate; in a standard reaction, 15 pmol  $\{0.6\mu M\}$ of the 5'-disulfide-containing oligodeoxynucleotide was incubated with 50 $\mu$ Ci (16.5 pmol, 0.66  $\mu$ M) of ( $\alpha$ -32P) dideoxyadenosine-5'triphosphate 10 (ddATP) (Amersham, Arlington Height, IL) in the presence of 0.2 mM 2mercaptoethanol. Upon the addition of 40 units of the terminal deoxynucleotidyl transferase enzyme (USB, Cleveland, OH), the reaction was allowed to proceed for one hour at 37°C. After this time, the reaction was stopped by immersion of the vial in 75°C water bath for ten minutes, and the product was isolated using a Chromaspin-10 column (Clontech, Palo Alto, CA). Similarly, a 5'-disulfide-containing oligodeoxynucleotide was radiolabeled with 35S.

In cases where a 3'-disulfide-containing oligodeoxynucleotide was to be immobilized, the 5'-terminus was radiolabeled using T4

20 polynucleotide kinase and a radiolabeled nucleoside triphosphate. For example, 15 pmol (0.6μM) of the 3'-disulfide-containing oligodeoxynucleotide was incubated with 50μCi (16.5pmol, 0.66μM) of (λ<sup>32</sup>P) adenosine-5'triphosphate (ATP) (Amersham, Arlington Height, IL) in the presence of 50 mM Tris-HCl, pH 7.6, 10 mM MgCl<sub>2</sub>, 10 mM 2-mercaptoethanol. Following the addition of 40 units of T4 polynucleotide kinase, the reaction was allowed to proceed for 1 hour at 37°C. The reaction was stopped by immersion of the vial in a 75°C water bath for ten minutes; the product was then isolated using a Chromaspin-10 column (Clontech, Palo Alto, CA).

To determine the density of covalently immobilized probe, the disulfide-containing oligodeoxynucleotide of choice was added to a trace amount of the same species than had been radiolabeled as described above. The disulfide was cleaved, the probe was immobilized on iodoacetamido-functionalized wafers, the wafers were washed, and then exposed to a phosphorimager screen (Molecular Dynamics, Sunnyvale, CA). For each different oligodeoxynucleotide used, reference spots were made on polystyrene in which the molar amount of aligodeoxynucleotide was known; these reference spots were exposed to the phosphorimager 10 screen as well. Upon scanning the screen, the quantity (in moles) of oligodeoxynucleotide bound to each chip was determined by comparing the counts to the specific activities of the references.

## Hybridization and Efficiency

To a wafer that had been functionalized with an immobilized probe was added a solution of a complementary sequence (10  $m \mu M$ ) in 1 M NaCl and TE buffer. The wafer and solution were heated to 75°C and allowed to cool to room temperature over 3 hours. After this time, the solution was removed, and the wafer was washed two times with TE buffer.

To determine the amount of oligonucleotide hybridized, immobilization of the probe was first carried out as described above except that the probe was labeled with 35S rather than 37P. The density of immobilized probe was determined with the phosphorimager. Next, the same wafer was incubated in TE buffer, 1 M NaCl, and its complementary strand (10 $\mu$ M) which had been radiolabeled with  $^{32}$ P. 25 Hybridization was carried out as previously described. Following a wash to remove non-specific binding, the wafer and reference were exposed to a phosphorimager screen with a piece of copper foil between the screen and the wafer. The copper foil serves to block the signal from 35S, while allowing the 32P signal to pass freely. The molar amount of hybridized

oligonucleotide is then determined, thus revealing the percent of covalently immobilized probe that is available for hybridization.

# MALDI-TOF Mass Spectrometric Analysis

As described above, wafers containing non-radiolabeled 5 immobilized oligodeoxynucleotide (name: TCUC; sequence: GAATTCGAGCTCGGTACCCGG; molecular weight; 6455 Da; SEQ ID NO. 1) were synthesized, and a complementary sequence (name: MJM6; sequence: CCGGGTACCGAGCTCGAATTC; molecular weight: 6415 Da; SEQ ID NO. 2) was hybridized. The waters were washed in 10 50mM ammonium citrate buffer for cation exchange to remove sodium and potassium ions on the DNA backbone (Pieles, U. et al., (1993) Nucl. Acids Res. 21:3191-3196). A matrix solution of 3-hydroxypicolinic acid (3-HPA, 0.7 M in 50% acetonitrile, 10% ammonium citrate; Wu, K.J., et al. (1993) Rapid Commun. Mass Spectrom. 7:142-146) was spotted 15 onto the wafer and allowed to dry at ambient temperature. The wafers were attached directly to the sample probe of a Finnigan MAT (Bremen, Germany) Vision 2000 reflectron TOF mass spectrometer using a conducting tape. The reflectron possesses a 5 keV ion source and 20 keV post-acceleration; a nitrogen laser was employed; and all spectra 20 were taken in the positive ion mode.

#### Surface Chemistry

Employing standard silicon dioxide modification chemistry, a silicon wafer was reacted with 3-aminopropyltriethoxysilane to produce a uniform layer of primary amino groups on the surface. As shown in Figure 7, the surface was then exposed to a heterobifunctional crosslinker resulting in iodoacetamido groups on the surface. It was possible to determine the optimal reaction time of this reaction in solution using TLC. The SIAB crosslinker was visualized under long wave ultraviolet light (302 nm) to reveal a spot with an R, value of 0.58, 3-

WO 99/31278

**-63**-

aminopropyltriethoxysilane was not active under ultraviolet light, therefore, ninhydrin was used to reveal a purple spot indicating the presence of a primary amine at the baseline. A microscale reaction was run using a slight molar excess of SIAB in comparison to 3-5 aminopropyltriethoxysilane; TLC analysis after approximately one minute revealed a new spot visible under long wave ultraviolet light with an R<sub>f</sub> value of 0.28. There was no evidence of a purple spot upon spraying with ninhydrin, thus all the 3-aminopropyltriethoxysilane starting material had been consumed in the reaction. UV light also revealed the excess 10 SIAB which remained following the reaction. From these results, it was determined the reaction is complete after approximately one minute. In all cases, the iodoacatamido-functionalized wafers were used immediately to minimize hydrolysis of the labile iodoacetamidofunctionality. Additionally, all further wafer manipulations were 15 performed in the dark since the iodoacetamido-functionality is light sensitive.

Disulfide reduction of the modified oligonucleotide was monitored by observing a shift in retention time on reverse-phase FPLC. It was determined that after five hours in the presence of DTT (100 mM) or TCEP (10 mM), the disulfide was fully reduced to a free thiol. If the DTT reaction was allowed to proceed for a longer time, an oligonucleotide dimer formed in which pairs of free thiols had reacted. Such dimerization was also observed when the DTT was removed following the completion of the cleavage reaction. This dimerization was not observed when TCEP was employed as the cleavage reagent since this reaction is performed at pH 4.5, thus the free thiols were fully protonated inhibiting dimerization.

Immediately following disulfide cleavage, the modified oligonucleotide was incubated with the iodacetamido-functionalized

wafers. To ensure complete thiol deprotonation, the coupling reaction was performed at pH 8.0. The probe surface density achieved by this chemistry of silicon wafers was analyzed using radiolabeled probes and a phosphorimager. The probe surface density was also monitored as a 5 function of the TCEP concentration used in the disulfide cleavage reaction (Figure 8). Using 10 mM TCEP to cleave the disulfide and the other reaction conditions described above, it was possible to reproducibly yield a surface density of 250 fmol per square mm of surface. Identical experiments as described above were performed except that the 10 oligonucleotide probe lacked a thiol modification; surface densities of less than 5 fmol per square mm of surface proved that non-specific binding is minimal and that probe coupling most likely occurred as proposed in Figure 7.

#### Hybridization

15

25

After attaching 35S-labeled probes to the surface of wafers and determining conjugation density as described above, hybridization of 32Plabeled oligonucleotides was carried out; hybridization efficiency and density were determined using the phosphorimager and copper foil. It was determined experimentally that copper foil blocks 98,4% of an 35S 20 signal, while fully allowing a <sup>32</sup>P signal to be detected. The complementary sequence reproducibly hybridized to yield 105 fmol per square mm of surface; this corresponds to approximately 40% of the conjugated probes available for hybridization. Similarly, a noncomplementary sequence was employed in this scheme yielding less than 5 fmol per square mm of surface in non-specific binding.

It is hypothesized that stearic interference between the tightly packed oligonucleotide on the flat surface inhibits hybridization efficiencies higher that 40%. With this in mind, a spacer molecule was incorporated between the terminus of the hybridizing r gion of the

oligonucleotide and the support. The chosen spacers were a series of poly dT sequences ranging in length from 3 to 25. Upon examination of these samples with radiolabels and the phosphorimager, it was determined that 40% was still the maximum hybridization that could be achieved.

## MALDI-TOF MS Analysis

Wafers were functionalized with probes, complementary sequences were hybridized, and the samples were analyzed under standard MALDI conditions as described above. Analysis revealed that 10 only the annealed strand (MJM6) was observed in the mass spectrum with an experimental mass-to-charge ratio of 6415.4; the theoretical mass-to-charge ratio is 6415 (Figure 9). Since there was no signal at a mass-to-charge ratio of 6455, it was determined that the waferconjugated strand (TCUC) was not described thus the iodoacetamido 15 linkage was stable enough to withstand the laser and remain intact. There was an additional signal observed at a mass-to-charge ration of 6262.0. This signal results from a depurination of guanosines since it is known that DNA is susceptible to the loss of purine bases during the MALDI process, [Nordoff, E., et al., (1992) Rapid Commun. Mass 20 Spectrom. 6:771-776). The sample crystals on the wafer were not homogeneously distributed, thus it was necessary to hunt for a good spot . Because of this non-homogeneity, the mass resolution varied, but it generally ranged from 200-300 for the described oligonuclectide in the mass spectra. In one set of experiments, non-complementary sequences 25 were hybridized to the wafer; following a wash as previously described, analysis by MALDI-TOF MS revealed that minimal non-specific annealing had taken place since no signal was detected.

-66-

#### **EXAMPLE 2**

# Preparation of DNA arrays using serial and parallel dispensing tools

Robot-driven serial and parallel pL-nL dispensing tools were used to generate 10-103 element DNA arrays on <1" square chips with flat or 5 geometrically altered (e.g. with wells) surfaces for matrix assisted laser desorption ionization mass spectrometry analysis. In the former, a 'piezoelectric pipette' (70  $\mu$ m id capillary) dispenses single or multiple ~0.2 nL droplets of matrix, and then analyte, onto the chip; spectra from as low as 0.2 fmol of a 36-mer DNA have been acquired using this procedure. Despite the fast (<5 sec) evaporation, micro-crystals of 3hydroxypicolinic acid matrix containing the analyte are routinely produced resulting in higher reproducibility than routinely obtained with larger volume preparations; all of 100 five fmol spots of a 23-mer in 800  $\mu m$ wells yielded easily interpreted mass spectra, with 99/100 parent ion 15 signals having signal to noise ratio of >5. In a second approach, probes from 384 well microtiter plate are dispensed 16 at a time into chip wells or onto flat surfaces using an array of spring loaded pins which transfer  $\sim\!20$  nL to the chip by surface contact; MS analysis of array elements deposited with the parallel method are comparable in terms of sensitivity and resolution to those made with the serial method.

# Description of the piezoslectric serial dispenser

The experimental system developed from a system purchased from Microdrop GmbH, Norderstedt Germany and can include a piezoslectric element driver which sends a pulsed signal to a piezoelectric element 25 bonded to and surrounding a glass capillary which holds the solution to be dispensed; a pressure transducer to load (by negative pressure) or empty (by positive pressure) the capillary; a robotic xyz stage and robot driver to maneuver the capillary for loading, unloading, dispensing, and cleaning, a stroboscope and driver pulsed at the frequency of the piezo

element to enable viewing of 'suspended' droplet characteristics; separate stages for source and designation plates or sample targets (i.e. Si chip); a camera mounted to the robotic arm to view loading to designation plate; and a data station which controls the pressure unit, xyz robot, and piezoelectric driver.

# Description of the parallel dispenser

The robotic pintool includes 16 probes housed in a probe block and mounted on an X Y, Z robotic stage. The robotic stage was a gantry system which enables the placement of sample trays below the arms of 10 the robot. The gantry unit itself is composed of X and Y arms which move 250 and 400 mm, respectively, guided by brushless linear servo motors with positional feedback provided by linear optical encoders. A lead screw driven Z axis (50 mm vertical travel) is mounted to the xy axis slide of the gantry unit and is controlled by an in-line rotary serve motor 15 with positional feedback by a motor-mounted rotary optical encoder. The work area of the system is equipped with a slide-out tooling plate that holds five microtiter plates (most often, 2 plates of wash solution and 3 plates of sample for a maximum of 1152 different oligonucleotide solutions) and up to ten 20x20 mm wafers. The wafers are placed 20 precisely in the plate against two banking pins and held secure by vacuum. The entire system is enclosed in plexi-glass housing for safety and mounted onto a steel support frame for thermal and vibrational damping. Motion control is accomplished by employing a commercial motion controller which was a 3-axis servo controller and is integrated to 25 a computer; programming code for specific applications is written as needed.

Samples were dispensed with the serial system onto several surfaces which served as targets in the MALDI TOF analysis including (1) A flat stainless steel sample target as supplied for routine use in a

Thermo Bioanalysis Vision 2000; (2) the same design stainless steel target with micromachined nanopits; (3) flat silicon (Si) wafers; (4) polished flat Si wafers; (5) Si wafers with rough (3-6 pLm features) pits; (6)(a) 12x12 or ((b) 18x18) mm Si chips with (a) 10x10 (or (b) 18x16) arrays of chemically etched wells, each 800x8001lm on a side with depths ranging from 99-400 (or(b) 120) micrometer, pitch (a) 1.0 (or(b) 1.125) mm; (7) 15x15 mm Si chips with 28x28 arrays of chemically etched wells, each 450x450 micrometer on a side with depths ranging from 48-300 micrometer, pitch 0.5 mm; (8)flat polycarbonate or other plastics; (9) gold and other metals; (10) membranes; (11) plastic surfaces sputtered with gold or other conducting materials. The dispensed volume is controlled from 10-10 to 10 fl by adjusting the number of droplets dispensed.

# Sample Preparation and Dispensing

### 15

#### Serial

Oligonucleotides (0.1-50 ng/microliter of different sequence or concentrations were loaded into wells of a 96 well microtiter plate; the first well was reserved for matrix solution. A pitted chip (target 6a in MALDI targets' section) was placed on the stage and aligned manually.

Into the (Windows-based) robot control software were entered the coordinates of the first well, the array size (ie number of spots in x and y) and spacing between elements, and the number of 0.2 nL drops per array element. The capillary was filled with ~ 10 µL rinse H<sub>2</sub>O, automatically moved in view of a strobe light-illuminated camera for checking tip integrity and cleanliness while in continuous pulse mode, and emptied. The capillary was then filled with matrix solution, again checked at the stroboscope, and then used to spot an array onto flat or pitted surfaces. For reproducibilty studies in different MS modes, typically a 10x10 array of 0.2-20 nL droplets were dispensed. The

capillary was emptied by application of positive pressure, optionally rinsed with  $H_2O$ , and led to the source oligo plate where  $\sim 5\mu L$  of 0.05-2.0 $\mu$ M synthetic oligo were drawn. The capillary was then rastered in series over each of the matrix spots with 0.2-20 nL aqueous solution added to each.

#### Parallel

Parallel Programs were written to control array making by offset printing; to make an array of 64 elements on 10 wafers, for example, the tool was dipped into 16 wells of a 3 84 well DNA source plate, moved to the target (e.g. Si, plastic, metal), and the sample spotted by surface contact. The tool was then dipped into the same 16 wells and spotted on the second target; this cycle was repeated on all ten wafers. Next the tool was dipped in washing solution, then dipped into 16 different wells of the source plate, and spotted onto the target 2.25 mm offset from the initial set of 16 spots; again this was repeated on all 10 wafers; the entire cycle was repeated to make a 2x2 array from each pin to produce an 8x8 array of spots (2x2 elements/pin X 16 pins = 64 total elements spotted).

To make arrays for MS analysis, oligonucleotides of different sequences or concentrations were loaded into the wells of up to three different 384-well microtiter plates, one set of 16 wells was reserved for matrix solution. The wells of two plates were filled with washing solution. The five microtiter plates were loaded onto the slide-out tooling plate. Ten wafers were placed abutting the banking pins on the tooling plate, and the vacuum turned on. In cases where matrix and oligonucleotide were not pre-mixed, the pintool was used to spot matrix solution first on all desired array elements of the ten wafers. For this example, a 16 x 16 array was created, thus the tool must spot each of the ten wafers 16 times, with an offset of 1.125 mm. Next, the

PCT/US98/26718 WO 99/31278

-70-

oligonucleotide solution was spotted in the same pattern to re-dissolve the matrix. Similarly, an array could be made by placing the oligonucleotide solution on the wafer first, followed by the matrix solution, or by pre-mixing the matrix and oligonucleotide solutions.

## Mass spectrometry

5

15

Subsequent to either dispensing scheme, loaded chips were held onto a MALDI-TOF source plate with a set of beveled screw mounted polycarbonated supports. The plate was transferred on the end of a probe to be held onto a 1  $\mu m$  resolution, 1" travel xy stage (Newport) in 10 the source region of a time-of-flight mass spectrometer. The instrument, normally operated with 18-26 kV extraction, could be operated in linear or curved field reflectron mode, and in continuous or delayed extraction mode.

# Serial dispensing with the piezoelectric pipette

While delivery of a saturated 3HPA solution can result in tip clogging as the solvent at the capillary-air interface evaporates, premixing DNA and matrix sufficiently dilutes the matrix such that it remains in solution while stable sprays which could be maintained until the capillary was emptied were obtained; with 1:1 diluted (in H<sub>2</sub>0) matrix 20 solution, continuous spraying for >> 10 minutes was possible. Turning off the piezo element so that the capillary sat inactive for >5 minutes, and reactivating the piezo element also did not result in a clogged capillary.

Initial experiments using stainless steel sample targets as provided by Finnigan Vision 2000 MALDI-TOF system run in reflectron mode used a pre-mixed solution of the matrix and DNA prior to dispensing onto the sample target. In a single microtiter well, 50µL saturated matrix solution,  $25\mu L$  of a  $51\mu L$  solution of the 12-mer (ATCG)3 (SEQ iD No. 3), and 25μL of a 51μL solution of the 28-mer (ATCG)7 (SEQ ID No. 4) were

mixed. A set of 10x10 arrays of 0.6µL drops was dispensed directly onto a Finnigan Vision 2000 sample target disk; MALDI-TOF mass spectrum was obtained from a single array element which contained 750 attornoles of each of the two oligonucleotides. Interpretable mass spectra has been obtained for DNA molecules as large as a 53-mer (350 amol loaded, not shown) using this method.

Mass spectra were also obtained from DNA molecules microdispensed into the wells of a silicon chip. Figure 10 shows a 12x12 mm silicon chip with 100 chemically etched wells; mask 10 dimensions and etch time were set such that fustum (i.e., inverted flat top pyramidal) geometry wells with 800x800 $\mu$ m (top surface) and 100 $\mu$ m depth were obtained. Optionally, the wells can be roughed or pitted. As described above, the chip edge was aligned against a raised surface on the stage to define the x and y coordinate systems with respect to the 15 capillary. (Alternatives include optical alignment, artificial intelligence pattern recognition routines, and dowel-pin based manual alignment). Into each well was dispensed 20 droplets (~5 nL) of 3-HPA matrix solution without analyte; for the 50% CH<sub>3</sub>CN solution employed, evaporation times for each droplet were on the order of 5-10 seconds. 20 Upon solvent evaporation, each microdispensed matrix droplet as viewed under a 120X stereomicroscope generally appeared as an amorphous and 'milky' flat disk; such appearances are consistent with those of droplets from which the Figure 3b spectrum was obtained. Upon tip emptying, rinsing, and refilling with a 1.4 $\mu$ m aqueous solution of a 23-mer DNA 25 (M<sub>i</sub>(calc) = 6967 Da), the capillary was directed above each of the 100 spots of matrix where 5 nL of the aqueous DNA solution was dispensed directly on top of the matrix droplets. Employing visualization via a CCD camera, it appeared that the aqueous analyte solution mixed with and redissolved the matrix (complete vaporation took ~ 10 sec at ambient

WO 99/31278 PCT/US98/26718

-72-

temperature and humidity). The amorphous matrix surfaces were converted to true micro-crystalline surfaces, with crystalline features on the order of <1  $\mu$ m.

Consistent with the improved crystallization afforded by the matrix re-dissolving method, mass spectrum acquisition appeared more reproducible than with pre-mixed matrix plus analyte solutions; each of the 100 five fmol spots of the 23-mer yielded interpreted mass spectra (Figure 11), with 99/100 parent ion signals having signal to noise ratios of >5; such reproducibility was also obtained with the flat silicon and metallic surfaces tried (not shown). The Figure 11 spectra were obtained on a linear TOF instrument operated at 26 kV. Upon internal calibration of the top left spectrum (well 'k1') using the singly and doubly charged molecular ions, and application of this calibration file to all other 99 spectra as an external calibration (Figure 12), a standard deviation of <9 Da from the average molecular weight was obtained, corresponding to a relative standard deviation of ~0.1%.

# Parallel dispensing with the robotic pintool

Arrays were made with offset printing as described above. The velocity of the X and Y stages are 35 inches/sec, and the velocity of the Z stage is 5.5 inches/sec. It is possible to move the X and Y stages at maximum velocity to decrease the cycle times, however the speed of the Z stage is to be decreased prior to surface contact with the wafer to avoid damaging it. At such axes speeds, the approximate cycle time to spot 16 elements (one tool impression of the same solutions) on all ten wafers is 20 seconds, so to make an array of 256 elements would take ~5.3 minutes. When placing different oligonucleotide solutions on the array, an additional washing step much be incorporated to clean the pin tip prior to dipping in another solution, thus the cycle time would increase to 25 seconds or 8.7 minutes to make 10 wafers.

20

Sample delivery by the tool was examined using radio-labeled solutions and the phosphorimager as described previously; it was determined that each pin delivers approximately 1 nL of liquid. The spotto-spot reproducibility is high. An array of 256 oligonucleotide elements 5 of varying sequence and concentration was made on flat silicon wafers using the pintool, and the wafer was analyzed by MALDI-TOF MS.

## **EXAMPLE 3**

Use of High Density Nucleic Acid Immobilization to Generate Nucleic Acid Arravs

Employing the high density attachment procedure described in EXAMPLE 1, an array of DNA oligomers amenable to MALDI-TOF mass spectrometry analysis was created on a silicon wafer having a plurality of locations, e.g., depressions or patches, on its surface. To generate the array, a free thiol-containing oligonucleotide primer was immobilized only 15 at the selected locations of the wafer (e.g., see Figure 13). Each location of the array contained one of three different oligomers. To demonstrate that the different immobilized oligomers could be separately detected and distinguished, three distinct oligonucleotides of differing lengths that are complementary to one of the three oligomers were. hybridized to the erray on the wafer and analyzed by MALDI-TOF mass spectrometry.

## Oligodeoxynucleotides

Three sets of complementary oligodeoxynucleotide pairs were synthesized in which one member of the complementary oligonucleotide 25 pair contains a 3'- or 5'-disulfide linkage (purchased from Operon Technologies or Oligos, Etc.). For example, Oligomer 1 (d(CTGATGCGTCGGATCATCTTTTT-SS); SEQ ID NO: 5) contains a 3'disulfide linkage whereas Oligomer 2 (d(SS-CCTCTTGGGAACTGTGTAGTATT); a 5'-disulfide derivative of SEQ ID

NO: 6) and Oligomer 3 (d(SS-GAATTCGAGCTCGGTACCCGG); a 5'-disulfide derivative of SEQ ID NO: 1) each contain a 5'-disulfide linkage.

The oligonucleotides complementary to Oligomers 1-3 were designed to be of different lengths that are easily resolvable from one another during MALDI-TOF MS analysis. For example, a 23-mer oligonucleotide (SEQ ID NO: 7) was synthesized complementary to a portion of Oligomer 1, a 12-mer oligonucleotide (SEQ ID NO: 8) was synthesized complementary to a portion of Oligomer 2 and a 21-mer (SEQ ID NO: 2; sequence denoted "MJM6" in EXAMPLE 1) was synthesized complementary to a portion of Oligomer 3. In addition, a fourth 29-mer oligonucleotide (SEQ ID NO: 9) was synthesized that lacks complementarity to any of the three oligomers. This fourth oligonucleotide was used as a negative control.

# Silicon surface chemistry and DNA immobilization

# 15 (a) 4 x 4 (16-location) array

A 2 X 2 cm² silicon wafer having 256 individual depressions or wells in the form of a 16 X 16 well array was purchased from a commercial supplier (Accelerator Technology Corp., College Station, Texas). The wells were 800 X 800 µm², 120 µm deep, on a 1.125 pitch. The silicon wafer was reacted with 3-aminopropyltriethoxysilane to produce a uniform layer of primary amines on the surface and then exposed to the heterobifunctional crosslinker SIAB resulting in iodoacetamido functionalities on the surface (e.g., see Figure 7).

To prepare the oligomers for coupling to the various locations of the silicon array, the disulfide bond of each oligomer was fully reduced using 10 mM TCEP as depicted in EXAMPLE 1, and the DNA resuspended at a final concentration of 10  $\mu$ M in a solution of 100 mM phosphate buffer, pH 8.0. Immediately following disulfide bond reduction, the free-thiol group of the oligomer was coupled to the

iodoacetamido functionality at 16 locations on the wafer using the probe coupling conditions essentially as described in Figure 7. To accomplish the separate coupling at 16 distinct locations of the wafer, the entire surface of the wafer was not flushed with an oligonucleotide solution 5 but, instead, an ~30-nl aliquot of a predetermined modified oligomer was added in parallel to each of 16 locations (i.e., depressions) of the 256 wells on the wafer to create a 4 x 4 array of immobilized DNA using a pin tool as described herein (see e.g., the Detailed Description and Example 4 provided herein).

Thus, as shown in Figure 13, one of modified Oligomers 1-3 was covalently immobilized to each of 16 separate wells of the 256 wells on the silicon wafer thereby creating a 4 x 4 array of immobilized DNA. For example, Oligomer 1 was conjugated at a well position in the upper left hand corner of the 4 x 4 erray and Oligomer 2 was conjugated to the 15 adjacent location, and so forth. An illustration of the completed array is shown in Figure 13.

in carrying out the hybridization reaction, the three complementary oligonucleotides and the negative control oligonucleotide were mixed at a final concentration of 10  $\mu$ M for each oligonucleotide in 1 ml of TE buffer 20 (10 mM Tris-HCl, pH 8.0, 1 mM EDTA) supplemented with 1 M NaCl, and the solution was heated at 65°C for 10 min. Immediately thereafter, the entire surface of the silicon wafer was flushed with 800  $\mu$ l of the heated oligonucleotide solution. The complementary oligonucleotides were annealed to the immobilized oligomers by incubating the silicon 25 array at ambient temperature for 1 hr, followed by incubation at 4°C for at least 10 min. Alternatively, the ofigonucleotide solution can be added to the wafer which is then heated and allowed to cool for hybridization. An illustration of the complementary oligonucleotides annealed to the

specific oligomers covalently immobilized at each location is shown in Figure 14.

The hybridized array was then washed with a solution of 50 mM ammonium citrate buffer for cation exchange to remove sodium and potassium ions on the DNA backbone (Pieles, U. et al., (1993) Nucl. Acids Res. 21:3191-3196). A 6-nl aliquot of a matrix solution of 3-hydroxypicolinic acid (0.7 M 3-hydroxypicolinic acid-10 % ammonium citrate in 50 % acetonitrile; see Wu et al., Rapid Commun. Mass Spectrom. 7:142-146 (1993)) was added to each location of the array using a piezoelectric pipette as described herein.

The solution was allowed to dry at ambient temperature and thereafter a 6-nl aliquot of water was added to each location using a piezoelectric pipette to resuspend the dried matrix-DNA complex, such that upon drying at ambient temperature the matrix-DNA complex forms a uniform crystalline surface on the bottom surface of each location,

## MALDI-TOF MS analysis

The MALDI-TOF MS analysis was performed in series on each of the 16 locations of the hybridization array illustrated in Figure 14 essentially as described in EXAMPLE 1. The resulting mass spectrum of oligonucleotides that specifically hybridized to each of the 16 locations of the DNA hybridization array is shown in Figure 15. The mass spectrum revealed a specific signal at each location representative of observed experimental mass-to-charge ratio corresponding to the specific complementary nucleotide sequence.

For example, in the locations that have only Oligomer 1 conjugated thereto, the mass spectrum revealed a predominate signal with an observed experimental mass-to-charge ratio of 7072.4 approximately equal to that of the 23-mer; the theoretical mass-to-charge ratio of the 23-mer is 7072.6 Da. Similarly, specific hybridization of the 12-mer

oligonucleotide to the array, observed experimental mass-to-charge ratio of 3618.33 Da (theoretical 3622.4 Da), was detected only at those locations conjugated with Oligomer 2 whereas specific hybridization of MJM6 (observed experimental mass-to-charge ratio of 6415.4) was 5 detected only at those locations of the array conjugated with Oligomer 3 (theoretical 6407.2 Dat.

None of the locations of the array revealed a signal that corresponds to the negative control 29-mer oligonucleotide (theoretical mass-to-charge ratio of 8974.8) indicating that specific target DNA 10 molecules can be hybridized to oligomers covalently immobilized to specific locations on the surface of the silicon array and a plurality of hybridization assays may be individually monitored using MALDI-TOF MS analysis.

#### 8 x 8 (64-location) array **(b)**

A 2 X 2 cm<sup>2</sup> silicon water having 256 individual depressions or wells that form a 16 X 16 array of wells was purchased from a commercial supplier (Accelerator Technology Corp., College Station, Texas ). The wells were 800 X 800  $\mu m^2$ , 120  $\mu m$  deep, on a 1.125 pitch. The silicon wafer was reacted with 3-aminopropyltriethoxysilene 20 to produce a uniform layer of primary amines on the surface and then exposed to the heterobifunctional crosslinker SIAB resulting in iodoacetamido functionalities on the surface (e.g., see Figure 7).

Following the procedures described above for the preparation of the 16-location DNA array, Oligomers 1-3 were immobilized to 64 locations forming an 8 X 8 array on the 256 well silicon wafer, hybridized to complementary oligonucleotides and analyzed by MALDI-TOF MS analysis. Figure 16 shows the mass spectrum of the 64location DNA array analyzed in series by MALDI-TOF analysis. As shown for the 16-location array, specific hybridization of the complementary

oligonucleotide to each of the immobilized thiol-containing oligomers was observed in each of the locations of the DNA array.

#### **EXAMPLE 4**

# RNA transcription of one-strand nicked DNA template

This example evaluates the effects of coding strand nick placement on the efficiency at which RNA transcripts are generated and also provides optimal conditions for generating RNA transcripts for sequencing.

# Design of Template and Primer Sequences

All primers were synthesized on a commercially available DNA

Synthesizer using conventional phosphoroamidite chemistry (Sinha et al.

(1984) Nucleic Acid Res. 12:4539). In vitro RNA transcription was performed on a synthetic 55 nucleotide double-stranded DNA template.

The template was assembled using three primer sequences; a 55 nucleotide noncoding strand (SEQ ID No: 10) and two additional primers that form the coding strand (SEQ ID Nos: 11 and 12). As shown in Figure 17, the specific position of the nick in the coding strand at a defined by the length of the each of the coding stand primers. Use of this construct for transcription demonstrated that a nick at this position does not substantially attenuate transcription.

# Primer Hybridization and RNA Transcription

One strand nicked templates were produced the hybridization of the three single-stranded oligonucleotides at a total DNA concentration of 10µM (2 fold excess of primers over template) in 10 mM MgCl<sub>2</sub> by heating the reaction mixture at 70°C for 10 minutes and cooling to room temperature for at least 4 hours. The position of the nick is determined by the corresponding lengths of the two coding strand (5′-3′) DNA oligonucleotides.

# SP6 RNA Polymerase Transcription

In vitro transcription of the nicked DNA templates was performed in 20 μl reactions of 40 mM Tris-HCl (pH 7.0), 6 mM MgCl<sub>2</sub>, 2 mM spermidine, 10 mM NaCl, 10 mM dithiothreitol, 1 unit/μl RNasin

5 (Promega), 5 mM rNTP, 5μCi (α-32P]rCTP, 1 unit/μl SP6 RNA polymerase (Amersham, Arlington Heights, IL) at 37°C for 30 minutes. Abortive and full length RNA transcripts were separated by gel electrophoresis and quantified by measuring the radioactivity of individual RNA fragments by drying the polyacrylamide gel and measuring the radioactivity as compared to a known standard using a Phospholmager (Molecular Dynamics, Inc.). The efficiency of full-length RNA transcription of a nicked DNA template was calculated as a percentage the moles of full length RNA transcribed from a DNA template containing no nicks. The nick by pass efficiency of a nicked DNA template was calculated as a percentage of the moles full-length RNA transcript and the moles of RNA transcript stalled at the nick,

As illustrated in Table 1, the transcription of a full-length RNA proceeds with 88-94% efficiency when a nick is introduced into the coding strand after nucleotides  $\pm 7$ ,  $\pm 8$ ,  $\pm 9$  or  $\pm 19$  relative to the start of transcription.

TABLE 1

	·			
	6-mer RNA (%)	Nick-stalled RNA (%)	Full-Length RNA (%)	Nick-Bypass Efficiency (%)
Ref.	320±93	•	(100)	100±0
1พ+7U	193.2±46.3	12.45.4	95.8±6.5	88.5±5.1
1N + 8U	187.4 ± 39.9	5.3 = 4,2	87.1 ± 4.3	94.3±0.5
1N + 9U	232.7±45.6	10.1 ± 1.1	65.7 ± 4.4	87.6±1.8
1N + 19U	279.6±33.8	6.6±0.3	64.8±4.5	90.9±0.4

25

-80-

## **EXAMPLE 5**

# DNA Sequencing using T7 RNA Polymerase

## Design of Template and Primer Sequences

All primers were synthesized on a commercially available DNA Synthesizer using conventional phosphoroamidite chemistry (Sinha et al. (1984) Nucleic Acid Res. 12:4539). In vitro RNA transcription was performed on a synthetic 276 nucleotide double-stranded DNA template (SEO ID No. 13, which includes a T7 promoter).

## 2. DNA Sequencing

DNA sequencing of a target DNA template was carried out in 10 μl reactions of 40 mM Tris-HCl (pH 7.9), 6 mM MgCl<sub>2</sub>, 2 mM neutralized spermidine, 5 mM dithiothreitol, 300 nM rCTP, 300 nM rATP, 300 nM rUTP, 300 nM rITP, 600 nM rGMP, 10 μCi (α-<sup>32</sup>P) rCTP or UTP, 10-300, generally 10-50 μM 3'-deoxynucleotide, 0.5-1.0 pmole linearized or supercoiled DNA template, 4 units RNasin (Promega), 10 unit/μl T7 RNA polymerase (USB) at 37°C for 30 minutes. Chain termination fragments RNA transcripts were separated by gel electrophoresis using 8% or 13% polyacrylamide gel.

DNA sequencing ladders of RNA terminated fragment were generated up to 180-200 bases. This example shows that T7 RNA polymerase can specifically incorporate modified 3'-deoxyribonucleosides triphosphates as a base-specific chain terminator to generate nested RNA transcripts for sequencing nucleic acids.

Since modifications will be apparent to those of skill in this art, it is intended that this invention be limited only by the scope of the appended claims.

### WHAT IS CLAIMED:

- A method for determining the sequence of a target nucleic acid molecule, comprising:
- a) providing a nucleic acid molecule comprising a promoter and
   5 target nucleic acid sequence operatively linked to the promoter, wherein the nucleic acid molecule is immobilized on a solid support;
  - b) transcribing the promoter-containing nucleic acid molecule with an RNA polymerase that recognizes the promoter under conditions whereby a nested set of RNA transcripts from the target is produced;
- 10 and
  - c) determining the molecular weight values of the transcripts by mass spectrometry and thereby determining the nucleic acid sequence of the target molecule.
  - The method of claim 1, wherein the promoter-containing
     nucleic acid molecule is immobilized via the 5' end of the coding strand or the 3' end of the non-coding strand.
    - 3. The method of claim 1, wherein the nucleic acid is DNA or PNA.
    - 4. The method of any of claims 1-3, wherein the nucleic acid molecule comprising a promoter and target is prepared by:
- 20 hybridizing a nucleic acid promoter-containing probe having a coding and noncoding strand to a nucleic acid molecule comprising a target nucleic acid sequence, wherein hybridization occurs between a single stranded region of the promoter-containing probe and a complementary single stranded region at one end of the molecule comprising the target.
  - 5. The method of claim 4, wherein the molecule comprising the target is single-stranded and the portion comprising the complementary single-stranded region is at the 3' end of the target-containing molecule;

and the promoter containing probe molecule is double-stranded with a single-stranded region of at least 5 nucleotides at the 3' end of the coding strand, wherein at least 5 contiguous nucleotides are complementary to the single-stranded portion of the target-containing molecule.

6. The method of claim 4, wherein:

the molecule comprising the target is double-stranded except for a single-stranded region at one end that comprises at least 5 contiguous nucleotides complementary to the single-stranded portion of the promoter-containing molecule; and

the single-stranded portion of the promoter-containing molecule is at same end, relative to the promoter, that the single-stranded region is on the target-containing molecule.

- 7. The method of any of claims 4-6, wherein the promoter-containing molecule is immobilized on the solid support prior to hybridization of the target-containing molecule.
- 8. The method of any of claims 4-6, wherein hybridization is performed prior to immobilization of the promoter-containing molecule on the solid support.
- 20 9. The method of any of claims 4-8, wherein nicks in the resulting molecules are ligated prior to transcription by the RNA polymerase.
- 10. The method of any of claims 1-9, wherein the nucleic acid molecule comprising a promoter and target nucleic acid is transcribed
  25 with an RNA polymerase to produce a plurality of base-specifically terminated RNA transcripts.
  - 11. The method of any of claims 1-9, wherein the nucleic acid molecule comprising a promoter and target nucleic acid is transcribed with an RNA polymerase to produce a set of RNA transcripts that are

then specifically cleaved with base-specific ribonucleases to produce a set of cleaved fragments whose molecule weight values are assessed by mass spectrometry.

- 12. The method of any of claims 1-11 wherein the sequence of
  all or a portion of the target nucleic acid is determined by the RNA transcripts according to molecular weight.
- 13. The method of any of claims 1-12, wherein the nucleic acid molecule comprising the promoter is produced by immobilizing a single-stranded molecule that comprises a promoter or the complement of a
  10 promoter and hybridizing a fragment that comprises the complement thereof, whereby the resulting molecule comprises a double-stranded region containing a promoter and a single-stranded portion of at least 5 nucleotides.
- 14. The method of any of claims 1-13, wherein the promoter is15 selected from the group consisting of phage, eukaryotic and prokaryotic promoters.
  - 15. The method of claim 14, wherein the promoter is selected from archaebacteria, eubecteria, bacteriophages, DNA viruses, RNA viruses, plants, plant viruses and animal promoters.
- 20 16. The method of any of claims 1-15, wherein the RNA polymerase is a DNA-dependent RNA polymerase or an RNA-dependent RNA polymerase.
- 17. The method of any of claims 1-16, wherein the RNA polymerase is selected from the group consisting of phage, eukaryotic and prokaryotic polymerases.
  - 18. The method of claim 17, wherein the polymerases is selected from archaebacteria, eubacteria, bacteriophages, DNA viruses, RNA viruses, plants, plant viruses and animal polymerases.


- 19. The method of any of claims 1-18, wherein the RNA polymerase is selected from the group consisting of Escherichia coli RNA polymerase, T7 RNA polymerase, SP6 RNA polymerase, T3 RNA polymerase and  $\Omega B$  replicase.
- 5 20. The method of any of claims 1-19, wherein prior to immobilization of the nucleic acid, the surface of the support is derivatized by reacting the surface with an aminosilane to produce primary amines on the surface of the support.
- 21. The method of claim 20, wherein the aminosilane is 3-10 aminopropyltriethoxysilane.
  - 22. The method of claim 21, further comprising reacting the primary amines on the surface of the support with a thiol-reactive cross-linking reagent to form a thiol-reactive solid support.
- 23. The method of claim 22, wherein the thiol-reactive cross-15 finking reagent is N-succinimidyl (4-iodoacetyl) aminobenzoate (SIAB).
  - 24. The method of claim 22, wherein the immobilization of the nucleic acid probe to a solid support is effected by reacting the thiol-reactive solid support with a nucleic acid probe having a free 5-' or 3'-thiol group, whereby a covalent bond between the thiol group and the thiol-reactive solid support is formed.
  - 25. The method of any of claims 1-21, wherein the nucleic acid molecule is immobilized to the surface the solid support at a density of at least 20 fmol/mm<sup>2</sup> by a covalent linkage.
- 26. The method of any of claims 1-25, wherein the nucleic acids25 are immobilized on the surface of the solid support in the form of an array.
  - 27. The method of any of claims 1-26, wherein the solid support is silicon or silicon coated.


- 28. The method of any of claims 1-27, wherein the surface comprises a plurality of wells comprising the immobilized nucleic acid molecule.
- 29. The method of claim 28, wherein the wells have a rough5 interior surface.
  - 30. The method of claim 28, wherein the solid support has a rough surface.
  - 31. The method of claim 28, wherein the surface of the wells is pitted.
- 32. The method of any of claims 1-31 wherein the transcription reactions are performed in the presence of a ribonucleoside triphosphate analog, whereby the resulting RNA transcripts have reduced secondary structure or the fidelity of termination and turnover of the RNA polymerase enzyme is increased compared to RNA transcripts formed from ribonucleoside triphosphatase.
  - 33. The method of claim 32, wherein the transcription reactions include one or more analogs selected from among inosine 5'-triphosphate (ITP), 4-thio uridine 5'triphosphate (UTP), 5-bromo UTP and 5'-iodo CTP.
- 34. The method of any of claims 1-33, wherein the nucleic acid20 is immobilized to the solid support via a linker.
  - 35. The method of claim 34, wherein the linkage formed by the linker is reversible.
  - 36. The method of claim 34, wherein the linkage formed by the linker is irreversible.
- 25 37. The method of claim 34, wherein the linkage formed by the linker is photolabile, acid labile or chemically cleavable.
  - 38. The method of any of claims 1-37, wherein transcription is performed in the presence of one or more 3'-deoxyribonucleotides.

- 39. The method of any of claims 1-38, further comprising: adding a matrix material for mass spectrometry to the surface of the support before or after immobilization of the nucleic acid.
- 40. The method of any of claims 1-39, wherein the RNA transcripts are conditioned prior to performing mass spectrometry.
- 41. The method of any of claims 1-4, wherein the hybridization of the nucleic acid containing the target sequence to the promoter-containing molecule results in the formation of a nick in the coding strand corresponding to positions beyond ±6 relative to the start of transcription from the promoter.
  - 42. The method of claim 24, wherein the nick is at position +7, +8, +9 or +19.
    - 43. The method of claim 1, comprising:
- a) immobilizing a nucleic acid promoter-containing probe on a solid support, wherein the nucleic acid promoter-containing probe comprises at least 5 nucleotides at the 3'-end of the coding strand that is complementary to a single-stranded region at the 3'-end of the target nucleic acid;
- b) hybridizing the nucleic acid to be sequenced to the 20 immobilized nucleic acid probe;
  - c) transcribing the target nucleic acid with an RNA polymerase to produce a plurality of base-specifically terminated RNA transcripts, wherein the RNA polymerase recognizes the promoter; and
- d) determining the molecular weight value of each
   25 base-specifically terminated RNA transcript by mass spectrometry.
  - 44. A method of identifying transcriptional terminator sequences or attenuator sequences, comprising:
  - a) immobilizing a nucleic acid promoter-containing probe on a solid support, wherein the nucleic acid promoter-containing probe


comprises at least 5 nucleotides at the 3'-end of the coding strand that is complementary to a single stranded region at the 3'-end of the target nucleic acid;

- b) hybridizing the nucleic acid to be sequenced to the5 immobilized nucleic acid probe;
  - c) transcribing the target nucleic acid with an RNA polymerase to produce a sequence-terminated RNA transcript, wherein the RNA polymerase recognizes the promoter; and
- d) determining the molecular weight value of the RNA
   10 transcript by mass spectrometry, whereby the terminator sequence or attenuator is identified.





**SUBSTITUTE SHEET (RULE 28)** 






FIG. 4

WO 99/31278 PCT/US98/26718




FIG. 5A




FIG. 5B

SUBSTITUTE SHEET (RULE 26)

WO 99/31278 PCT/US98/26718




FIG. 5C




FIG. 5D

SUBSTITUTE SHEET (RULE 26)




FIG. 6A




FIG. 6B





FIG. 8



SUBSTITUTE SHEET (RULE 26)




FIG. 10

23-MER (6nL of 1.4uM = 8.6fmol) 10x10 850x850um (89um DEPTH) WELLS.





FIG. | |

k1	k2	kJ	k4	k5	k6	k7	k8	k9	k10
6968 Da	6968 Da	6988 Da	6977 Do	6971 Dø	6968 Do	6972 Da	6978 0a	6952 Do	6965 Do
170 RP	100 RP	90 RP	100 RP	170 RP	110 RP	160 RP	110 RP	250 RP	300 RP
11	12	13	14	15	16	17	18	19	110
6965 Dc	6989 Do	6982 Do	6996 Do	6982 Do	6968 Do	6984 Do	6968 Do	5996 Do	6968 Do
130 RP	140 RP	210 RP	50 RP	160 RP	180 RP	130 RP	200 RP	80 RP	100 RP
m1	m2	m3	m4	m5	m6	m7	m8	m9	m10
6966 Da	6979 Da	6975 Da	6968 Da	6976 Do	6986 Do	6973 Oo	6978 Da	6975 Do	6955 Da
190 RP	120 RP	120 RP	190 RP	110 RP	120 RP	160 RP	160 RP	230 RP	<b>250</b> RP
n1	n2	n3	л <b>4</b>	п5	n6	n7	n8	n9	n10
6961 Do	6971 Do	6970 Da	6960 Do	6985 Da	6953 Do	6971 Do	6962 Do	6957 Do	6960 Da
340 RP	180 RP	150 RP	300 RP	120 RP	210 RP	140 RP	160 RP	150 RP	160 RP
o1 6965 Do 140 RP	o2 6960 Do 230 RP	o3 6976 Da 200 RP	o4 6953 Da 250 RP	o5 6983 Do 110 RP	<b>c6</b> 6967 Da 250 RP	6970 Do 150 RP	o8 6973 Da 70 RP	o9 6953 Do 140 RP	o10 6952 Do 140 RP
p1	p2	p3	p4	p5	ρ6	p7	p8	p9	p10
6976 Da	6981 Do	6972 Da	6969 Da	6984 Da	6968 Do	6958 Do	6981 Do	6978 Do	6965 Da
140 RP	90 RP	180 RP	90 RP	130 RP	100 RP	290 RP	100 RP	110 RP	150 RP
q1	q2	q3	q4	q\$	96	q7	<b>98</b>	99	q10
6976 Da	6985 Do	6990 Da	6989 Da	6984 Do	6969 Da	6979 Da	6968 Do	6973 Do	6950 Do
170 RP	100 RP	120 RP	90 RP	90 RP	170 RP	70 RP	140 RP	120 RP	120 RP
r1	r2	r3	r4	r5	r6	r7	r8	r9	r10
6966 Do	6960 Da	6969 Do	6964 Do	6966 Do	6970 Da	6972 Do	6939 Do	6951 Do	6965 Do
130 RP	150 RP	100 RP	180 RP	130 RP	110 RP	90 RP	130 RP	230 RP	200 RP
s1	s2	s3	s4	s5	s6	\$7	<b>s8</b>	s9	s10
6963 Da	6953 Do	6970 Do	6971 Do	6957 Da	6956 0⊲	6966 Do	6975 Da	6951 Da	6969 Da
130 RP	210 RP	120 RP	170 RP	130 RP	160 RP	140 RP	120 RP	230 RP	120 RP
11	t2	t3	t4	t5	16	17	t8	(9	110
6974 Do	6958 Do	6959 Da	6952 Do	6959 Da	6954 Da	6950 0a	6974 Da	6967 Do	6950 Do
90 RP	160 RP	120 RP	100 RP	110 RP	100 RP	160 RP	140 RP	150 RP	230 R₽


LASER POWER = 41000 FOR ALL SPECTRA. EACH SPECTRUM THE SUM OF 10-30 SINGLE SHOTS.

FIG. 12

WO 99/31278 PCT/US98/26718



SUBSTITUTE SHEET (RULE 26)



SUBSTITUTE SHEET (RULE 26)





FIG. 15



SUBSTITUTE SHEET (RULE 26)

Nick +7 U Stort of Transcription

<u>-1G. 17</u>

#### SEQUENCE LISTING

#### (1) GENERAL INFORMATION

#### (i) APPLICANT:

- (A) NAME: SEQUENON, INC.
  (B) STREET: 11555 Sorrento Vailey Road
- (C) CITY: San Diego (C) STATE: California (E) COUNTRY: USA

- (F) POSTAL CODE (ZIP): 92121

### (i) APPLICANT:

- (A) NAME: KOREA ADVANCED INSTITUTE OF SCIENCE AND TECHNOLOGY
- (A) MANE: KOREA ADVANCED INSTI (B) STREET: 373-L Kusong-dong (C) CITY: Tacjen 305 701 (D) STATE: Yusong-gu (E) COUNTRY: Republic of Korea (F) POSTAL CODE (ZIP): 32121

#### (i) INVENTOR

- (A) NAME: Changwon Kang
- (B) STREET: Expo Apt. 305-401, 464-1 Jeonmin-dong

- (C) CITY: Taejon 305-390 (D) STATE: Yusong gu (D) COUNTRY: REPUBLIC OF KOREA (E) POSTAL CODE (ZIP):

#### (i) INVENTOR

- (A) NAME: Young-Soo Kwon (B) STREET: 25-2 Mangwol-dong
- (C) CITY: Kwangju 500-500 (D) STATE: Puk-gu
- (D) COUNTRY: Republic of Korea
- (B) POSTAL CODE (ZIP):

## (i) INVENTOR:

- (A) NAME: Young Tae Kim
  (B) STREFT: Sungwon Apt. 2 204, 162 Songpa-2-dong
  (C) CITY: Seoul 138-172
  (D) STATE: Songpa-gu

- (D) COUNTRY: REPUBLIC
- (E) POSTAL CODE (ZIP):

## (1) INVENTOR:

- (A) NAME: Hubert Köster (B) STREET: 836 Via Mallorca Drive
- (C) CITY: La Jolla
- (D) STATE: California
- (D) COUNTRY: USA
- (E) POSTAL CODE (ZIP): 92037

### (i) INVENTOR:

- (A) NAME:
- (A) NAME: Daniel P. Little
  (B) STREET: 393 Glendale Lake Rd.
- (C) CITY: Patton (D) STATE: Pennsylvania (D) COUNTRY: USA
- (E) POSTAL CODE (ZIP): 18668

WO 99/31278

- (i) INVENTOR: (A) NAME: Maryanne C'Donnell (B) STREET: (C) CITY:

  - (D) STATE:

  - (D) COUNTRY: (E) POSTAL CODE (ZIP):
- (1) INVENTOR:
  - (A) NAME: Goubing Kiang
  - (B) STREET: 11391 Zapata Ave.
  - (C) CITY: Sam Diego (D) STATE: California

  - (D) COUNTRY: USA
  - (E) POSTAL CODE (ZIP): 92126
- (i) INVENTOR:
  - (A) NAME: Charles Cantor

  - (B) STREBT: (C) CITY: (D) STATE: California
  - (D) COUNTRY: USA
  - (E) POSTAL CODE (ZIP):
- (i) INVENTOR:
  - David Lough
  - (A) NAME: (B) STREET:
  - (C) CITY:

  - (D) STATE: (D) COUNTRY: USA
  - (E) POSTAL CODE (ZIP):
- (ii) TITLE OF INVENTION: MASS SPECTROMETRIC METHODS FOR SEQUENCING NUCLETC ACIDS
  - (iii) NUMBER OF SEQUENCES: 13
  - (iv) CORRESPONDENCE ADDRESS:
    - (A) ADDRESSER: Heller Ehrman White & McAuliffe
    - (B) STREET: 4250 Executive Square, 7th Floor
    - (C) CITY: La Jolla
    - (D) STATE: CA
    - (E) COUNTRY: USA
    - (P) ZIP: 92037
  - (v) COMPUTER READABLE FORM:
    - (A) MEDIUM TYPE: Diskette
    - (R) COMPUTER: TEM Compatible (C) OPERATING SYSTEM: DOS

    - (D) SOFTWARE: ASCII
  - (vL) CURRENT APPLICATION DATA:
    - (A) APPLICATION NUMBER:
    - (B) FILING DATE:
    - (C) CLASSIFICATION:
  - (vii) PRIOR APPLICATION DATA:

(A) AFPLICATION NUMBER: 08/990,651 (B) FILING DATE: 15-DEC-1997	
<pre>(viii) ATTORNEY/AGENT INFORMATION:   (A) NAME: Seidman, Stephanie L   (B) REGISTRATION NUMBER: 33,779   (C) REFERENCE/DOCKET NUMBER: 24735-2007</pre>	
(ix) TELECOMMUNICATION INFORMATION: (A: TELEPEONE: 619-450-8400 (B) TELEPAX: 615-450-8499	
(2) INFORMATION FOR SEQ ID NO:1:	
<ul> <li>(i) SEQUENCE CHARACTERISTICS:</li> <li>(A) LENGTH: 21 base pairs</li> <li>(B) TYFE: nucleic acid</li> <li>(C) STRANDEENESS: single</li> <li>(D) TOPOLOGY: unknown</li> </ul>	
(ii) MOLECULE TYPR: cDNA (iii) HYPOTHETICAL: NO (iv) ANTISENSE: NO (v) PRAGMENT TYPE: (vi) ORIGINAL SOURCE:	
(xi) SEQUENCE DESCRIPTION: SEQ ID NO:1:	
B DDDDATENDE TUKETACCCG G	21
(2) INFORMATION FOR SEO ID NO:2:	
(i) SROURNCE CHARACTERISTICS: (A) LENGTH: 21 base pairs (B) TYPE: nucleic acid (C) STRANDEDNESS: Gingle (D) TOPOLOGY: unknown	
(!i) MOTECULE TYPE: CDNA (!ii) BYPOTHETICAL: NO (!v) ANTISENSE: NO (v) FRACMENT TYPE: (vi) DRIGINAL SOURCE:	
(xi) SEQUENCE DESCRIPTION: SEQ ID NO:2:	
COGGGTACCG AGCTCGAATT C	2
(2) INFORMATION FOR SEQ ID NO:3:	
(i) SEQUENCE CHARACTERISTICS: (A) LENGTH: 12 base pairs (B) TYPE: nucleic acid (C) STRANDEDNESS: unknown (D) TOPOLOGY: unknown	
(ii) MOLECULE TYPE: CDNA (iii) HYPOTHETICAL: NO (iv) ANTISENSE: NO	

PCT/US98/26718

(v) FRACMENT TYPE: (vi) ORIGINAL SOURCR:	
(xi) SEQUENCE DESCRIPTION: SEQ ID NO:3:	
ATCGATCGAT CG	12
(2) INFORMATION FOR SEQ ID NO:4:	
(1) SEQUENCE CHARACTERISTICS: (A) LENGIH: 2E basc pairs (3) TYFE: nucleic acid (C) STRANDEDNESS: single (D) TOFOLOGY: unknown	
<pre>(ii: MOLECULE TYPE: cDNA (iii) HYFOTHETICAL: NO (iv) ANTISENSE: NO (v) FRAGMENT TYPE: (vi) ORIGINAL SOURCE:</pre>	
(x2) SEQUENCE DESCRIPTION: SEQ ID NO:4:	
ESTADDIA COTADDIADO CARDIAGOTA	28
(2) INFORMATION FOR SEQ ID NO:5:	
(i) SEQUENCE CHARACTERISTICS: (A) LENGTH: 24 base pairs (B) TYPE: nucleic acid (C) STRANDEDNESS: single (D) TOPOLOGY: unknown	
<pre>(ii) MOLECULE TYPE: cDNA (iii) NYPOTHETICAL: NO (iv) ANTISENSE: NO (v) FRAGMENT TYPE: (vi) ORIGINAL SOURCE:</pre>	
(xi) SEQUENCE DESCRIPTION: SEQ ID NO:5:	
CTGATGCGTC GGATCATCIT ITTT	24
(2) INFORMATION FOR SEQ ID NC:6:	
(1) SEQUENCE CEARACTERISTICS: (A) LENGTH: 23 base pairs (B) TYPE: nucleic acid (C) STRANDEDNESS: unknown (D) TOPOLOGY: unknown	
(ii) MOLECULE TYPE: CDNA (iii) HYPOTHETICAL: NO (iv) ANTISENSE: NO (v) FRAGMEDT TYPE: (vi) ORIGINAL SOURCE:	
(xi) SEQUENCE DESCRIPTION: SEQ ID NO:6:	

23

CCTCTTGGGA ACTGTGTAGT ATT

(2) INFORMATION FOR SEQ ID NO:7:	
(i) SEQUENCE CHARACTERISTICS:  (A) LENGIH: 23 base pairs  (B) TYPE: nucleic acid  (C) STRANDEDNESS: single  (D) TOPOLOGY: unknown	
(ii) MCLECULE TYPE: CDNA (iii) HYPOTHETICAL: NO (iv) ANTIGENSE: NO (v) FRACMENT TYPE: (vi) ORIGINAL SOURCE:	
(xi) SEQUENCE DESCRIPTION: SEQ ID NO:7:	
GATGATCCGA CGCATCAGAA TGT	23
(2) INFORMATION FOR SEQ IE NO:8:	
(1) SEQUENCE CHARACTERISTICS:  (A) LENGTH: 12 base pairs  (B) TYPE: nucleic acid  (C) STRANDEDNESS: single  (D) TOPOLOGY: unknown	
(ii) MOLECULE TYPE: dDMA (iii) HYPOTEETICAL: NO (iv) ANTISENSE: NO (v) FRAGMENT TYPE: (vi) ORIGINAL SOURCE:	
(xi) SEQUENCE DESCRIPTION: SEQ ID MO:8:	
AATACTACAC AG	12
(2) INFORMATION FOR SEQ ID NO:9:	
(i) SEQUENCE CHARACTERISTICS: (A) LENGTH: 29 base pairs (3) TYFE: nucleic acid (C) STRANDRONESS: unknown (D) TOPOLOGY: unknown	
<ul> <li>(ii) MOLECULE TYPR: cDNA</li> <li>(iii) HYPOTHETICAL: NO</li> <li>(iv) ANTISENSE: NO</li> <li>(v) FRAGMENT TYPE:</li> <li>(v¹) ORIGINAL SOURCE:</li> </ul>	
(x1) SEQUENCE DESCRIPTION: SEQ ID NO:9:	
GATCTAGCTG GGCCGAGCTA GGCCGTTGA	29
(2) INFORMATION FOR SEQ ID NO:10:	
(i) SEQUENCE CHARACTERISTICS: (A) LENGTH: 55 base pairs (b) TYPE: nucleic acid (C) STRANDEDNESS: single (D) TOPOLOGY: unknown	

```
(ii) MOLECULE TYPE: CDNA
        (iii) MYPOTHETICAL: NO
        (iv) ANTISENSE: NO
        (v) FRAGMENT TYPE:
(vi) ORIGINAL SOURCE:
        (xi) SEQUENCE DESCRIPTION: SEQ ID NO:10:
ATAGACGCTG CTGGACGGCA CCCTTCTCCA ACACTTCTAT ACTCTCACCT AAATC 55
           (2) INFORMATION FOR SEQ 1D NO:11:
        (i) SEQUENCE CHARACTERISTICS:
          (A) LENGTH: 25 base pairs
           (B) TYPE: nucleic acid
           (C) STRANDEDNESS: Single (D) TOFOLOGY: ubknown
        (ii) MOLECULE TYPE: CDNA
        (iii) HYPOTHETICAL: NO
        (iv) ANTISENSE: NO
        (v) FRACMENT TYPE:
        (v1) ORIGINAL SOURCE:
        (xi) SEQUENCE DESCRIPTION: SEQ ID NO:11:
                                                            25
GATTTAGGTG ACACTATAGA AGTCT
           (2) INFORMATION FOR SEC ID NO:12:
        (i) SEQUENCE CHARACTERISTICS:
          (A) LENGTH: 30 base pairs
(B) TYPE: mucleic acid
(C) STRANDEUNESS: unknown
           (D) TOPOLOGY: unknown
        (ii) MOLECULE TYPE: cDNA
        (iii) HYPOTHETICAL: NO
        (iv) ANTISENSE: NO
(v) PRAGMENT TYPE:
(vi) ORIGINAL SOURCE:
        (xi) SEQUENCE DESCRIPTION: SEQ ID NO:12:
```

(2) INFORMATION FOR SEQ ID NO:13:

(i) SEQUENCE CHARACTERISTICS:

- (A) LENGTH: 276 base pairs
- (B) TYPE: nucleic acid (C) STRANDEDNESS: single
- (D) TOPOLOGY: unknown
- (ii) MOLECULE TYPE: cCNA
- (iii) HYPOTHETICAL: NO
- (iv) ANTISENSE: NO

TGGAGAAGGG TGCCSTCCAS CAGCGTCTAT

- (v) FRAGMENT TYPE:
- (vi) ORIGINAL SOURCE:
- (xi) SEQUENCE DESCRIPTION: SEQ ID NO:13:

WO 99/31278 PCT/US98/26718

CCTCTAATAC	GACTCACTAT	AGGGAGACAA	GCTIGCATGC	CTGCAGGTCG	ACTCTAGAGG	60
ATCÇÇÇGGGT	ACCGAGCTCG	AATTCCTGGC	AGTTTATGGC	GGGCGTCTGC	CACCCTCCGG	120
GCCCTTGCTT	CGCAACGITC	AAAICCCCCT	CCCGCCGATT	TOTOCTACIO	AGGAGAGCGT	180
TCACCCGACA	AACAACAGAT	алалалала	CCCAGTCTIT	CGACTGGGCC	TITCCTTTTA	240
TTTGATGCCT	TUUTTAAEDD	ATTCTATTCT	ATAGTG			276

# INTERNATIONAL SEARCH REPORT

information on patent family members

Intern: JAI Application No PCT/US 98/26718

	terit document in search report		Publication date		atent family member(s)		Publication date
WO	9632504	A	17-10-1996	AU	5544696	A	30-10-1996
				CA	2218188	A	17-10-1996
				£Ρ	0830460	Д	25-03-1998
				JP	11503611	T	30-03-1999
WO	9737041	A	09-10-1997	AU	2217597	A	22-10-1997
EP	0785278	A	23-07-1997	CA	2204378	Α	17-05-1996
				WO	9614434	A	17-05-1996
US	5571669	٨	05-11-1996	NOME			<b>L</b>
ή0 	8907149	A	10-08-1999	ΕP	0358737	A	21-03-1990
ЙO	9605323	Α	22-02-1996	FR	2723591	A	16-02-1996
				AT	165870	T	15-05-1998
				DE	69502402	D	10-06-1998
				ÐΕ	69502402	T	10-12-1998
				EP	0775217	A	28-05-1997

# INTERNATIONAL SEARCH REPORT

Intern. .al Application No PCT/US 98/26718

IPC 6	IFICATION OF SUBJECT MATTER C1201/68			
According 1	to Infomational Paters Classification (IPC) or to both religional छउट	sdication and IPC		
	SEARCHED			
Minimum di 1PC 6	pour remailion securitied. (classification system followed by classification system followed by classificati	ication symbols;		
IFC 0	C12Q			
Documents	it the extent to industrient upon the control of the extent in the exten	es chief er i ni bebulani ats charusob rous ter	orched	
Electronic o	date base consulted during the international search (name of cate	a base and, where practics, sewich lunns used	<del></del>	
	COURT AND PARS SA BU BRI BY ANT			
	ŒNTS CONSIDERED TO BE RELEVANT			
Category *	Claten of document, with indication, where appropriate, of the	ə miavəni prossagsa	Flakvam to daim No.	
Y	WO 96 32504 A (UNIV BOSTON) 17 October 1996 see claims 1-27		1-44	
Y	WO 97 37041 A (SEQUENOM INC) 9 October 1997 see page 24, line 10 - line 27		1-44	
γ	EP 0 785 278 A (INST OF PHYSIC, CHEMICAL RE) 23 July 1997 see the whole document	AL &	1-44	
Y	US 5 571 669 A (LU PONZY ET A 5 November 1996 see page 1, column 1 - column		\-44	
		-/	i	
			_	
X Far	ther popuments are listed in the continuation of box C.	Cetsil era sradmem ylimist method	ন হ্ৰানex.	
, Rbeciar o	: Snarruded baha sa sesse terre	anti entraliz bedeilaug Insnumbo tetal	maternal filling date	
	nent defining the general state of the lan which is not	the following the critical of the control of the critical of t	trø apolication but	
E' semer	rderad to be of particular relovance I document but published on of after the international	X° cocument of particular relayance. The o	cial med invention	
"L" docum white:	ra (kimiala ylbona no stabob worlit yeni "ostwi man radiona to etko nojisoikug erti delildelse oz balio si ":	cannot be considered and or cannot be do particular and described of the formation and particular relations of the formation of the formation and the format	ourrent a takan eko 18	
'O' docur	*O" document referring to an and displacation, use, exhibition or discussion is combined with one or more other such docu-			
יאי שמענד	ণ লক্ষ্য ক mark published prior to the imemational filing date but Theat the priority data distinct	media, succ combination being covid in the act.  3: dod_ment marmar of the acces cotem	•	
	n artiful combine on a, the Automational estatch	Cate of mailing of the international 69	· · · · · · · · · · · · · · · · · · ·	
:	23 April 1999	03/05/1999		
Verne and	I mailing occinase of the ISA European Patent Cifice, P.B. 5818 Patentican 2	Aufhorized afficer		
	NL - 2200 HV Fillewik Tal.   - 31-70) 343-2040, Tx. 31 651 epp ml. Fax: (-31-70) 340-3016	Osborne, H		

# INTERNATIONAL SEARCH REPORT

PCT/US 98/26718

		FC1703 96720716
	nton) DOCUMENTS CONSIDERED TO BE RELEVANY  Citation of Socurron, with Indication where appropriate, of the relevant passages	Relevant to claim No.
rumajciy -	Cration of Suburiors, with Protestion while a sport options. Of the 1993/2011 becoming a	POSTATE DE CAPITING.
A	WO 89 07149 A (MAYO FOUNDATION) 10 August 1989 see the whole document	1-44
A	WO 96 05323 A (CIS BIO INT ;SAUVAIGO SYLVIE (FR); BAZIN HERVE (FR); LIVACHE THIER) 22 February 1996 see abstract	
	· · · · · · · · · · · · · · · · · · ·	